CONTRACT NO. 68770

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
698	127I	WOODFORD	7	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

20200600 EXCAVATING AND GRADING FOR EXISTING SHOULDERS

	LOCATION			UNITS
	STA.	to STA.		
LT	202+89	208+55.29		5.7
LT	208+55.29	209+47.71	Bridge Omission SN 102 - 0044	
LT	209+47.71	240+80.75		31.3
LT	240+80.75	241+94	Bridge Omission SN 102 - 0045	
LT	241+94	339+85		97.9
RT	202+89	208+55.29		5.7
RT	208+55.29	209+47.71	Bridge Omission SN 102 - 0044	
RT	209+47.71	240+80.75		31.3
RT	240+80.75	241+94	Bridge Omission SN 102 - 0045	
RT	241+94	339+85		97.9
			TOTAL	269.8

28000500 INLET & PIPE PROTECTION

LOCATION	EA
STA.	
217+05	3
220+35	2
275+21	2
299+85	2
316+06	2
326+27	3
TOTAL	14

48102100 AGGREGATE WEDGE SHOULDER, TYPE B

	LOCATION			TON
	STA.	to STA.		
LT	202+89	208+55.29		16.12
LT	208+55.29	209+47.71	Bridge Omission SN 102 - 0044	
LT	209+47.71	240+80.75		89.2
LT	240+80.75	241+94	Bridge Omission SN 102 - 0045	
LT	241+94	339+85		278.77
RT	202+89	208+55.29		16.12
RT	208+55.29	209+47.71	Bridge Omission SN 102 - 0044	
RT	209+47.71	240+80.75		89.2
RT	240+80.75	241+94	Bridge Omission SN 102 - 0045	
RT	241+94	339+85		278.77
			TOTAL	768.2

48203029 HOT-MIX ASPHALT SHOULDERS, 8"

	LOCATION			SQ YD
	STA.	to STA.		
LT	202+89	208+55.29		314.6
LT	208+55.29	209+47.71	Bridge Omission SN 102 - 0044	
LT	209+47.71	240+80.75		1740.56
LT	240+80.75	241+94	Bridge Omission SN 102 - 0045	
LT	241+94	339+85		5439.4
RT	202+89	208+55.29		314.6
RT	208+55.29	209+47.71	Bridge Omission SN 102 - 0044	
RT	209+47.71	240+80.75		1740.56
RT	240+80.75	241+94	Bridge Omission SN 102 - 0045	
RT	241+94	339+85		5439.4
			TOTAL	14989.1

64200105 SHOULDER RUMBLE STRIP

	LOCATION			FT
	STA.	to STA.		
LT	202+89	208+55.29		566.29
LT	208+55.29	209+47.71	Bridge Omission SN 102 - 0044	
LT	209+47.71	240+80.75		3133.04
LT	240+80.75	241+94	Bridge Omission SN 102 - 0045	
LT	241+94	339+85		9791
RT	202+89	208+55.29		566.29
RT	208+55.29	209+47.71	Bridge Omission SN 102 - 0044	
RT	209+47.71	240+80.75		3133.04
RT	240+80.75	241+94	Bridge Omission SN 102 - 0045	
RT	241+94	339+85		9791
			TOTAL	26980.7

67100100 MOBILIZATION

LOCATION			L SUM
STA.	to	STA.	
202+89		339+85	1
		TOTAL	1

70100500 TRAFFIC CONTROL AND PROTECTION, STANDARD 701326

LOCATION			L SUM
STA.	to	STA.	
202+89		339+85	1
		TOTAL	1

70100460 TRAFFIC CONTROL AND PROTECTION, STANDARD 701306

LOCATION			L SUM
STA.	to	STA.	
202+89		339+85	1
		TOTAL	1

70103815 TRAFFIC CONTROL SURVEILLANCE

LOCATION			CAL DA
STA.	to	STA.	
202+89		339+85	14
		TOTAL	14

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 2/1/2008
FILE NAME = S:\GENLDRAFT\STDRPLNS\SDA013\68778\68778.dgn
PLOT SCALE = 100.0000 / IN.
USER NAME = bogarmaj