

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
639	(123B)-2	MERCER	15	2
STA. 151+26.40		TO STA. 157+20.66		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

COMMITMENTS

The Contractor and Resident Engineer shall contact the D4 I.D.O.T. Materials Department for exact aggregate optimized class BD mix design. Overlay mix shall be conventional BD mix with additional 10% cement material.

GENERAL NOTES

Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

The proposed replacement Concrete Wearing Surface shall be hand-tined as per Article 420.09(e)(1) of the Standard Specifications. The cost of this work shall be incidental to "Concrete Wearing Surface".

PLOT DATE : 08/16/2007 11:07
 FILE NAME : I:\FILES\GEN\DRIFT\STAMP\MS\SOUND\BRIDGE Cont\68772\68772-8886\17over-EdwardsRvr.dgn
 PLOT SCALE : 1"=20'
 REFERENCE :

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SCALE: VERT.
 HORIZ.
 DATE 08-16-2007

DRAWN BY CEJ
 CHECKED BY