

F.A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
639	(1238)1-2	MERCER	15	6
STA. 151+26.40 TO STA. 157+20.66				
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

SCHEDULE OF QUANTITIES

EPOXY PAVEMENT MARKING LINE, 4" & PAVEMENT MARKING REMOVAL

LOCATION STA. TO STA.	LENGTH (FOOT)	PVMT. MRKG. REM.	
		WHITE EDGE LINE (SQ.FT.)	YELLOW SKIP DASH (SQ.FT.)
Sta. 148.47 to Sta. 157.21	874	262.2	
Sta. 148+37 to Sta. 157+81	315		94.5
Sta. 150+27 to Sta. 156+00	573	172	
TOTAL	1762	529	

PAVEMENT MARKING TAPE & WORKZONE PAVEMENT MARKING REMOVAL

LOCATION STA. TO STA.	TEMP. PVMT. MRKG. LINE - 4" WHITE (FT.)	TEMP. PVMT. MRKG. LINE - 4" WHITE (FT.)	WORK ZONE PVMT. MRKG. REM. (FT.)
Sta. 148+47.11 to Sta. 150+51.11		240 (Taper)	240 (Taper)
Sta. 150+51.11 to Sta. 155+05.00		454 (C)	454 (C)
Sta. 155+05.00 to Sta. 157+21.00		216 (Taper)	216 (Taper)
Sta. 150+27.11 to Sta. 155+55.00	530.0 (N.Edge)		530.0 (N.Edge)
SUB-TOTAL	530.0	874	
TOTAL		1404	1404

TEMPORARY TRAFFIC SIGNALS

LOCATION	TRAFFIC SIGNALS (EA.)
Jobsite Traffic Control	1
TOTAL	1

TRAFFIC CONTROL

LOCATION STA. TO STA.	TEMP. CONC. BARRIER (FT)	IMPACT ATTEN. TEMP. (EACH)	T,C,&P. STANDARD 701201 (EACH)	T,C,&P. STANDARD 701321 (EACH)	T,C,&P. STANDARD 701326 (EACH)
Sta. 149+89 to Sta. 155+80	588				
Jobsite		2	1	1	1
TOTAL	588	2	1	1	1

BITUMINOUS WIDENING MIX SPECIFICATION

The following mixture requirements are applicable to this project:

MIXTURE USE(S):	SURFACE LIFT	LOWER LIFTS
AC/PG:	PG 64-22	PG 64-22
RAP% (MAX): **	30% Max	30% Max
Design Air Voids:	3.0% @ N=30	4.0% @ N=30
Mixture Composition: (Graduation Mixture)	IL. 9.5L	IL 19.0L
Friction Aggregate:	Mixture C	N/A

** If RAP option is selected, the asphalt cement grade may need to be adjusted by the Materials Engineer.

SHOULDER REMOVAL/REPLACEMENT

BITUMINOUS CONCRETE SHOULDER REMOVAL			
LEFT WEST APPROACH	SQ.YD.	LEFT EAST APPROACH	SQ.YD.
Sta. 151+01.11 to Sta. 151+26.11	58		N/A
RIGHT WEST APPROACH		RIGHT EAST APPROACH	
	N/A		N/A
TOTAL			58
HMA BASE COURSE WIDENING, 9"			
LEFT WEST APPROACH	SQ.YD.	LEFT EAST APPROACH	SQ.YD.
Sta. 151+01.11 to Sta. 151+26.11	58		N/A
RIGHT WEST APPROACH		RIGHT EAST APPROACH	
	N/A		N/A
TOTAL			58

SN.066-0006 IL.17
over Edwards River

NOTE
Additional pay items that may not be included in the SCHEDULE OF QUANTITIES pertain to the superstructure repair and are designated on the Bridge Office Repair Details, (pages 14-16). Signing on Sheet 13.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE: 01-14-2008

DRAWN BY CEJ
CHECKED BY