

SUMMARY OF QUANTITIES

		100% STATE SAFETY-2A HENDERSON COUNTY		
CODE NO.	ITEM	UNIT	RURAL	TOTAL
20200500	EARTH EXCAVATION (WIDENING)	CU YD	91	91
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4	4
40600525	LEVELING BINDER (HAND METHOD), N50	TON	9	9
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	13.6	13.6
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	26.3	26.3
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	325	325
50102400	CONCRETE REMOVAL	CU YD	13.0	13.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	13.0	13.0
50300300	PROTECTIVE COAT	SQ YD	49	49
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	1,015	1,015
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,350	1,350
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	121	121
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	515	515
67000400	ENGINEER ^{'S} FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1

		100% STATE SAFETY-2A HENDERSON COUNTY		
CODE NO.	ITEM	UNIT	RURAL	TOTAL
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	8
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	176	176
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	704	704
70400100	TEMPORARY CONCRETE BARRIER	FOOT	425	425
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	425	425
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1582	1582
* 78200530	BARRIER WALL REFLECTOR, TYPE C	EACH	4	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	294	294
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	1,030	1,030
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	14
Z0001900	ASBETOS BEARING PAD REMOVAL	EACH	6	6
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL3	EACH	2	2

*SPECIALTY ITEM