

SCHEDULE OF QUANTITIES

LOCATIONS STA. TO STA.	HMA SURF CSE	HMA BINDER COURSE = IL - 19.0	LEVELING BINDER (HAND METHOD), N50
	TON	TON	TON
RT STA 64+00 TO 65+49	7.24	36.18	
RT STA 66+83 TO 68+28	13.53	67.66	
LT STA 64+40 TO 65+63	5.36	26.78	
LT STA 66+97 TO 68+15	5.14	25.70	
BRIDGE DECK	14.7	0	10*
TOTAL	45.97	156.32	10

* Estimated quantity for waterproofing lift and leveling binder lift

LOCATIONS STA. TO STA.	WATERPROOFING MEMBRANE SYSTEM
	SQ YD
STA 65+56.27 TO 66+89.89	135
TOTAL	135

LOCATIONS STA. TO STA.	TEMPORARY CONCRETE BARRIER	RELOCATE TEMP CONC BARRIER
	FOOT	FOOT
TAPER STA 64+16.83 TO 65+29.33	112.5	112.5
TANGENT STA 65+29.33 TO 67+16.83	187.5	187.5
TAPER STA 67+16.83 TO 69+04.33	112.5	112.5
TOTAL	412.5	412.5

LOCATIONS STA. TO STA.	REMOVE & REPLACE EXISTING RAILING	CONCRETE SUPERSTRUCTURE	HMA SURF CSE REM
	FOOT	CU YD	SQ YD
STA 65+56.27 TO 66+89.89	42	1.7	23.7
TOTAL	42	1.7	23.7

LOCATIONS STA. TO STA.	SHORT - TERM PAVEMENT MARKING
	FOOT
STA. 62+83 TO 69+63	1360
TOTAL	1360

LOCATIONS STA. TO STA.	IMPACT ATT TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATT RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
	EACH	EACH
STA 64+16.83	1	1
STA 69+04.33	1	1
TOTAL	2	2

LOCATIONS STA. TO STA.	P P CONC DECK BEAM (27' DEPTH)	REM OF EXIST P P CONC DECK BEAMS	ASBESTOS BEARING PAD REMOVAL
	SQ FT	SQ FT	EACH
STA 65+56.27 TO 66+89.89	1,028	1,042	3
TOTAL	1,028	1,042	3

LOCATIONS STA. TO STA.	PROTECTIVE COAT
	SQ YD
STA 65+56.27 TO 66+89.89	12.4
TOTAL	12.4

LOCATIONS STA. TO STA.	BIT MAT (PRIME COAT)
	GALLON
ROADWAY	9
STRUCTURE	4
TOTAL	13

LOCATIONS STA. TO STA.	MOBILIZATION	T C & PROT STANDARD 701321	ENGINEER FIELD OFFICE TYPE A	TEMPORARY BRIDGE TRAFFIC SIGNAL	TEMPORARY RUMBLE STRIP	T C & PROT STANDARD 701316
	L SUM	EACH	CAL. MO.	EACH	EACH	EACH
JOBSITE	1	1	3	1	6	1
TOTAL	1	1	3	1	6	1

LOCATIONS STA. TO STA.	CHANGEABLE MESSAGE SIGN
	CAL DAY
* East of Job	7
* West of Job	7
TOTAL	14

* To be placed 7 days prior to placing Barrier Wall at locations designated by the Engineer.