

SCHEDULE OF QUANTITIES

LOCATIONS STA. TO STA.	PAVEMENT REMOVAL *
	SQ YD
RT STA 64+00 TO 65+49	65
RT STA 66+83 TO 68+28	121
LT STA 64+40 TO 65+63	48
LT STA 66+97 TO 68+15	46
TOTAL	280

* REMOVE 12 INCHES

LOCATIONS STA. TO STA.	TR CONT SURVEILLANCE	RAILROAD PROTECTIVE LIABILITY INSURANCE
	CAL DAY	L SUM
JOBSITE	12	1
TOTAL	12	1

LOCATIONS STA. TO STA.	P C MORTAR FAIRING COURSE
	FOOT
STRUCTURE STA 65+56.27 TO 66+89.89	523
TOTAL	523

LOCATIONS STA. TO STA.	PAVT MARKING REMOVAL	PAINT PAVEMENT MARKING LINE 4"
	SQ FT	FOOT
⊘ STA 62+83 TO 69+63 - DOUBLE YELLOW	454	1360
LT STA 62+83 TO 69.63 - EDGELINE	227	680
RT STA 62+83 TO 69.63 - EDGELINE	227	680
TOTAL	908	2720

LOCATIONS STA. TO STA.	RAISED REF PAVT MK REM
	EACH
BRIDGE SPANS WITH BEAM 6 REPLACEMENT	5
BRIDGE - SOUTH SPAN	2*
NORTH SIDE OF BRIDGE	15*
SOUTH SIDE OF BRIDGE	14*
TOTAL	36

* REMOVE OR COVER LENSES

LOCATIONS STA. TO STA.	WORK ZONE PAVEMENT MARKING REMOVAL
	SQ FT
STD 701326 STAGE 1 CENTERLINE & EDGELINE STA 62+83 TO 69+63	454
STD 701326 STAGE 2 CENTERLINE & EDGELINE STA 62+83 TO 69+63	454
STD 701326 STOPBARS	96
STD 701321 STAGE 1 CENTERLINE & EDGELINE STA 62+83 TO 69+63	454
STD 701321 STAGE 2 CENTERLINE & EDGELINE STA 62+83 TO 69+63	454
STD 701321 STOPBARS	96
SHORT TERM PAVEMENT MARKINGS - DOUBLE YELLOW CENTERLINE	454
TOTAL	2462

LOCATIONS STA. TO STA.	RAISED REF PAVT MK BR
	EACH
BRIDGE SPANS WITH BEAM 6 REPLACEMENT	5
TOTAL	5