

# SUMMARY OF QUANTITIES

		100% STATE SAFETY-2A FULTON COUNTY		
CODE NO.	ITEM	UNIT	RURAL	TOTAL
20200500	EARTH EXCAVATION WIDENING	CU YD	280	280
25100630	EROSION CONTROL BLANKET	SQ YD	3,388	3,388
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SQ YD	1,120	1,120
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	40	40
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	22	22
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	11	11
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	1,188	1,188
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	159	159
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	143	143
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	396	396
67000400	<sup>C/S</sup> ENGINEER FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1	1

		100% STATE SAFETY-2A FULTON COUNTY		
CODE NO.	ITEM	UNIT	RURAL	TOTAL
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	800	800
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	270	270
70400100	TEMPORARY CONCRETE BARRIER	FOOT	312.5	312.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	312.5	312.5
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,800	1,800
78300100	PAVEMENT MARKING REMOVAL	SQ FT	540	540
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	1,188	1,188
X0325569	TEMPORARY BRIDGE TRAFFIC SIGNALS RESIDENTIAL APPROACH	EACH	1	1
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	11	11
X7011830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	EACH	2	2
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	14
X7016500	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	EACH	1	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2

\*SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 317	SECTION (137-8R-1H-1)	COUNTY FULTON	TOTAL SHEETS 12	SHEET NO. 3
#FILE#	PLOT SCALE = #SCALE#	DRAWN -	REVISED -		SCALE:					
	PLOT DATE = #DATE#	CHECKED -	REVISED -		STA.	TO STA.	FED. ROAD DIST. NO.	US 24	FED. AID PROJECT	CONTRACT NO. 66782