

## SUMMARY OF QUANTITIES

LOCATION OF WORK: FAS 1517 (US 150)  
PIATT COUNTY  
  
STA. 4+89.42  
STA. 5+60.59

CONSTRUCTION TYPE CODE: 100% STATE  
SFTY-2A  
TOTAL  
QUANTITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
50102400	CONCRETE REMOVAL	CU YD	1.0
50300300	PROTECTIVE COAT	SQ YD	101.0
50301200	CONCRETE WEARING SURFACE	SQ YD	101.0
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	854.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,190.0
67100100	MOBILIZATION	L SUM	1.0
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1.0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	415.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	225.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,395.0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	235.0
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	854.0
X0321781	MECHANICAL SPLICE	EACH	72.0
<del>50900905</del>	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	73.0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0

\* SPECIALTY ITEM

FILE NAME = c:\projects\4570699\70699\plans.dgn	USER NAME = collierbw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.S. RTE. 1517	SECTION DS BEAM REPLACE 2008-2	COUNTY PIATT	TOTAL SHEETS 18	SHEET NO. 4
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	REVISED -	SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 70699
PLOT DATE = 2/6/2008	DATE -	REVISED -	REVISED -							