

## SCHEDULES OF QUANTITIES

### 70400100 TEMPORARY CONCRETE BARRIER

<u>STATION</u>	<u>OFFSET (FT)</u>	<u>TO</u>	<u>STATION</u>	<u>OFFSET (FT)</u>	<u>LENGTH (FT)</u>
4+12.68	5.92 LT		4+62.50	1.77 LT	50.00
4+62.50	1.77 LT		5+87.50	1.77 LT	125.00
5+87.50	1.77 LT		6+37.32	5.92 LT	50.00
TOTALS =					225.00
USE					<u>225.00</u>

### Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-DIRECTIVE), TEST LEVEL 3

<u>STATION</u>	<u>OFFSET (FT)</u>	<u>EACH</u>
4+12.68	5.92 LT	1.00
6+37.32	5.92 LT	1.00
TOTALS =		<u>2.00</u>
USE		<u>2.00</u>