

SUMMARY OF QUANTITIES		UNITS	TOTAL QUANTITY
			<i>X081-2A 100% STATE</i>
PAY CODE NUMBER	PAY ITEM DESCRIPTION		
50300300	<i>PROTECTIVE COAT</i>	<i>SQ YD</i>	<i>117.60</i>
50301200	CONCRETE WEARING SURFACE	SQ YD	117.60
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	959.00
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2960.00
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	54.00
67100100	MOBILIZATION	L SUM	1.00
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1.00
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1.00
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1.00
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2.00
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	170.00
X0301424	SILICONE JOINT SEALER	FOOT	28.00
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	959.00
X0320887	POLYMER CONCRETE	CU FT	1.00
X0321781	MECHANICAL SPLICE	EACH	187.00
X5030275	CONCRETE WEARING SURFACE REMOVAL	SQ YD	10.40
<i>Z0001900</i>	<i>ASBESTOS BEARING PAD REMOVAL</i>	<i>EACH</i>	<i>6</i>

**SPECIALTY ITEMS*

Rev.

FILE NAME : SUMMARY OF QUANTITIES	USER NAME : laughlin1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 745	SECTION (108BR)1-1	COUNTY PIKE	TOTAL SHEETS 7	SHEET NO. 3	
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT
	PLOT DATE = Feb-11-2008 07:12:44AM	DATE -	REVISED -			CONTRACT NO. 72B57					
<i>*SPECIALTY ITEMS</i>											