

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	19RS-4	SHELBY	33	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 00: FED. / 20: STATE 1000
CODE NO	ITEM	UNIT		
20800150	TRENCH BACKFILL	CU YD	29	29
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.1	0.1
28000500	INLET AND PIPE PROTECTION	EACH	2	2
28100207	STONE RIPRAP, CLASS A4	TON	50	50
28200200	FILTER FABRIC	SQ YD	58	58
35650700	BASE COURSE WIDENING	SQ YD	180	180
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	118	118
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	14310	14310
40600300	AGGREGATE (PRIME COAT)	TON	286	286
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	6002	6002
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	347	347
40600990	TEMPORARY RAMP	SQ YD	58	58
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	12020	12020
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	277	277
44000100	PAVEMENT REMOVAL	SQ YD	93	93
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	142751	142751
44004000	PAVED DITCH REMOVAL	FOOT	80	80
44201863	CLASS D PATCHES, TYPE II, 18 INCH	SQ YD	1873	1873
44201867	CLASS D PATCHES, TYPE III, 18 INCH	SQ YD	198	198
44201869	CLASS D PATCHES, TYPE IV, 18 INCH	SQ YD	304	304
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2629	2629
50105220	PIPE CULVERT REMOVAL	FOOT	104	104
54215547	METAL END SECTIONS 12"	EACH	2	2
54215559	METAL END SECTIONS 24"	EACH	2	2
54248510	CONCRETE COLLAR	CU YD	2	2
542A0265	PIPE CULVERTS, CLASS A, TYPE 1 60"	FOOT	47	47
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	42	42
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	55	55
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1875	1875
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	9	9
63200310	GUARDRAIL REMOVAL	FOOT	1050	1050
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	25	25

SUMMARY OF QUANTITIES (Cont'd)			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 00: FED. / 20: STATE 1000
CODE NO	ITEM	UNIT		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2	2
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14796	14796
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	47	47
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	123213	123213
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	109	109
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	307	307
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1644	1644
70400100	TEMPORARY CONCRETE BARRIER	FOOT	225	225
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	225	225
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	47	47
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4967	4967
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	109	109
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	307	307
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	118246	118246
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	673	673
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	24	24
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	9	9
78300100	PAVEMENT MARKING REMOVAL	SQ FT	200	200
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	141	141
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: VERT. HORIZ. DATE 01-08

DRAWN BY RWS CHECKED BY