

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	19RS-4	SHELBY	33	7

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

RESURFACING SCHEDULE		LENGTH	AVERAGE PAVEMENT WIDTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	LEVELING BINDER (MACHINE METHOD), N70	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	
STATION	TO STATION	FOOT	FOOT	SQ YD	SQ YD	GALLON	TON	TON	TON	TON	SQ YD	SQ YD	
913+65.00	TO 913+95.00	30.0	26.0	86.7	0.0	8.7	0.2	7.3	0.0	1.7	86.7	14.4	
913+95.00	TO 914+00.00	5.0	26.0	14.4	14.4	1.4	0.0	1.2	0.3	0.3			
914+00.00	TO 1082+37.56	16837.6	26.0	48641.8	48641.8	4864.2	97.3	4085.9	2043.0	914.8			
1082+37.56	BK= 1082+37.70 AH												
1082+37.70	TO 1097+22.95	1485.3	26.0	4290.7	4290.7	429.1	8.6	360.4	180.2	82.9			
1097+22.95	BK= 1097+22.30 AH												
1097+22.30	TO 1159+95.00	6272.7	26.0	18121.1	18121.1	1812.1	36.2	1522.2	761.1	338.1			
1159+95.00	TO 1173+00.00	1305.0	VAR	0.0	5170.0	517.0	10.3	434.3	217.1	59.3			
1173+00.00	TO 1189+77.32	1677.3	26.0	4845.6	4845.6	484.6	9.7	407.0	203.5	84.6			
1189+77.32	BK= 1190+25.87 AH												
1190+25.87	TO 1244+03.75	5377.9	26.0	15536.1	15536.1	1553.6	31.1	1305.0	652.5	291.5			
1244+03.75	TO 1244+08.75	5.0	26.0	14.4	14.4	1.4	0.0	1.2	0.6	0.3			
1244+08.75	TO 1244+38.75	30.0	26.0	86.7	0.0	8.7	0.2	7.3	3.6	1.7	86.7	14.4	
1244+38.75	TO 1245+17.25	78.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0			
1245+17.25	TO 1245+47.25	30.0	26.0	86.7	0.0	8.7	0.2	7.3	3.6	1.7	86.7	14.4	
1245+47.25	TO 1245+52.25	5.0	26.0	14.4	14.4	1.4	0.0	1.2	0.6	0.3			
1245+52.25	TO 1273+55.64	2803.4	26.0	8098.7	8098.7	809.9	16.2	680.3	340.1	150.2			
1273+55.64	BK= 1274+58.48 AH												
1274+58.48	TO 1336+27.03	6168.6	26.0	17820.3	17820.3	1782.0	35.6	1496.9	748.5	323.7			
1336+27.03	BK= 1336+22.42 AH												
1336+22.42	TO 1368+91.00	3268.6	26.0	9442.6	9442.6	944.3	18.9	793.2	396.6	175.7			
1368+91.00	BK= 1368+92.00 AH												
1368+92.00	TO 1406+05.00	3713.0	26.0	10726.4	10726.4	1072.6	21.5	901.0	450.5	200.5			
1406+05.00	TO 1406+10.00	5.0	26.0	14.4	14.4	1.4	0.0	1.2	0.3	0.3			
1406+10.00	TO 1406+40.00	30.0	26.0	86.7	0.0	8.7	0.2	7.3	0.0	1.7	86.7	14.4	
TOTALS					137928.0	142751.0	14310.0	286.0	12020.0	6002.0	2629.0	347.0	58.0

PLOT DATE = 1/29/2008  
 FILE NAME = c:\projects\74144\ah\ahsch\_74144.dgn  
 PLOT SCALE = 56.0000' / 1"  
 USER NAME = smortz

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SHEET 1 OF 3

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_