

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		100% STATE SFTY-2A
35650700	BASE COURSE WIDENING	SQ YD	177	177
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	23	23
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	30.2	30.2
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	1354	1354
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	378	378
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	181	181
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	529	529
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1011	1011
70400100	TEMPORARY CONCRETE BARRIER	FOOT	637.5	637.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	637.5	637.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2318	2318
78300100	PAVEMENT MARKING REMOVAL	SQ FT	430	430
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	1360	1360
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2

* SPECIALTY ITEMS