

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
304	5BR-2	CALHOUN	68	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		I000-2A FED 80% STATE 20%	X071 -2A FED 80% STATE 20%
* 7800650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	20	20	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	705		705
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2		2
* 78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	4	4	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	840	840	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1
X7200200	WIDE LOAD SIGNING	L SUM	1	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

PLOT DATE = 1/30/2008
 FILE NAME = c:\projects\76948\plan\p1091005a.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 REFERENCE = #REF*

*SPECIALTY ITEMS