

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE 1000	100% STATE Y031-1F	-----	CODE NO	ITEM	UNIT		-----	-----	-----
*81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	70		70								
*81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1		1								
*87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	370		370								
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	300		300								
*88500100	INDUCTIVE LOOP DETECTOR	EACH	1		1								
*88600100	DETECTOR LOOP, TYPE I	FOOT	334		334								
*89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	825		825								
*89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	5291		5291								
*89502380	REMOVE EXISTING HANDHOLE	EACH	2		2								
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1158	1158									
X4421000	PARTIAL DEPTH PATCHING	TON	129	129									
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	765	765									
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	308	308									
25100630	EROSION CONTROL BLANKET	SQ YD	4081	4081									
28000300	TEMPORARY DITCH CHECKS	EACH	7	7									
28000400	PERIMETER EROSION BARRIER	FOOT	4119	4119									
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	6675	6675									

* SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 674	SECTION 410, 410-1-I	COUNTY ST. CLAIR	TOTAL SHEETS 41	SHEET NO. 3A
#FILE#		DRAWN -	REVISED -							
		CHECKED -	REVISED -							
		DATE -	REVISED -							

Rev.