

PAVEMENT MARKING SCHEDULE - IL 158

LOCATION				THERMOPLASTIC PAVEMENT MARKING								SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 8"	TEMPORARY PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
				SOLID WHITE, 4"	SKIP-DASH WHITE, 4"	SOLID YELLOW, 4"	DOUBLE SOLID YELLOW, 4"	SOLID WHITE, 8"	SOLID WHITE, 12"	SOLID YELLOW, 12"	SOLID WHITE, 24"								
STATION	TO	STATION	SB/NB	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	
IL 158 @ WHERRY ROAD																			
188+79	TO	197+80	SB/NB	1,826.5	426.5	1,970.0		646.5			38.8	500.2	4,223.0	646.5		38.8	2,081.7	110	92
197+80	TO	206+76	SB/NB	2,262.4	418.8	1,921.6		607.3			53.0	532.6	4,602.8	607.3		53.0	2,221.2	110	101
IL 158 @ SIEBERT ROAD																			
237+70	TO	246+20	SB/NB	1,955.8	397.3	1,898.1		593.7	55.3		46.9	494.8	4,251.2	593.7	55.3	46.9	2,125.5	108	89
246+20	TO	254+33	SB/NB	1,800.6	385.8	1,182.1		555.8	39.4		36.6	411.4	3,368.5	555.8	39.4	36.6	1,742.0	115	84
PROFILE CORRECTIONS - IL 158																			
288+20	TO	297+26	NB	906.0	226.5	906.0						247.1	2,038.5				761.1	12	12
289+10	TO	297+33	SB	823.0	205.8	823.0						224.5	1,851.8				691.4	11	11
BRIDGE OMISSION																			
299+95	TO	307+00	SB	705.0	176.3	705.0						192.3	1,586.3				592.2	9	9
300+14	TO	306+75	NB	661.0	165.3	661.0						180.3	1,487.3				555.3	9	9
IL 158 @ IL 161																			
333+25	TO	351+40	SB/NB	3,707.1	626.8	3,250.7		1,617.3	865.9		78.1	860.4	7,584.6	1,617.3	865.9	78.1	4,913.0	46	103
WHERRY ROAD																			
1182+00	TO	1191+40		2,220.3		692.7	2,085.6	238.2	180.3	126.1	54.3	359.6	4,998.6	238.2	306.4	54.3	2,358.2		14
SIEBERT ROAD																			
1106+50	TO	1114+75		1,768.3	204.3	925.2	1,085.8	233.2	165.0	43.8	55.9	368.5	3,983.6	233.2	208.8	55.9	1,925.4		17
SUBTOTALS				18,636.0	3,233.0	14,935.4	3,171.4	4,492.0	1,305.9	169.9	363.6	4,371.7	39,975.8	4,492.0	1,475.8	363.6	19,966.9	530	541
TOTALS (ROUNDED FOR SUMMARY)					39,976			4,492	1,476		364	4,372	39,976	4,492	1,476	364	19,967	530	541