

F.A.I.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	22	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• FAS 1909 & FAP 322 ** D9 PAVEMENT PRESERVATION FY08 *** JACKSON AND UNION COUNTIES				

US 51 LOCATIONS 1 & 2
RAISED REFLECTIVE PAVEMENT MARKERS

IL 127 LOCATION 3
RAISED REFLECTIVE PAVEMENT MARKERS

STATION TO STATION				RAISED REF PAVT MARKERS			NOTES
				CLEAR - ONE WAY	AMBER - ONE WAY	AMBER - TWO WAY	
				EACH	EACH	EACH	
US 51 LOCATION 1 - STA. 1000+33 TO STA. 238+50							
	1000+34.0	TO	1000+46.0	3			PAINTED ISLAND
LT	1000+44.0	TO	LT 1003+13.0	8			LANE LINE
RT	1000+41.0	TO	RT 1000+56.0	3			PAINTED ISLAND
	1000+50.0	TO	1010+23.0		53		MEDIAN
	1010+23.0	TO	1011+64.0			8	CENTERLINE
	1011+64.0	TO	1027+93.0			21	CENTERLINE
	1027+93.0	TO	1028+79.0			6	CENTERLINE
	1028+79.0	TO	1032+07.0		20		MEDIAN
RT	1032+50.0	TO	LT 1038+20.0			32	MEDIAN
LT	1032+50.0	TO	LT 1034+50.0	4			LANE LINE
RT	1037+20.0	TO	RT 1038+20.0	6			LANE LINE
LT	1038+93.0	TO	LT 1039+93.0	4			LANE LINE
RT	1038+93.0	TO	RT 1039+93.0			8	
RT	1039+93.0	TO	1044+78.0		22		MEDIAN
	1044+78.0	TO	1047+55.6			16	
EQ STA 1047+55.55 (BK) = STA 52+01.25 (AH)							
	52+01.3	TO	64+21.6			63	CENTERLINE
	64+21.6	TO	81+81.0			23	CENTERLINE
	81+81.0	TO	103+30.8			28	CENTERLINE
EQ STA 103+30.75 (BK) = STA. 103+86.85 (AH)							
	103+86.9	TO	116+31.0			17	
	116+31.0	TO	118+04.6			3	CENTERLINE
EQ STA 118+04.60 (BK.) = STA. 2018+04.60 (AH.)							
	2018+04.6	TO	2081+74.0			81	CENTERLINE
EQ STA 2081+73.95 (BK) = STA 187+61.39 (AH)							
	187+61.4	TO	238+50.0			65	CENTERLINE
SUBTOTAL LOCATION 1				28	95	370	
TOTAL LOCATION 1					493		
US 51 LOCATION 2 - STA. 238+50 TO STA. 378+65							
	238+50.0	TO	240+04.2			3	CENTERLINE
EQ STA 3040+04.17 (BK) = STA 3073+50 (S.N. 091-0071)							
	3040+04.2	TO	3073+50.0			43	CENTERLINE
OMIT S.N. 091-0071 STA. 3073+50 TO STA. 3075+71							
	3075+71.0	TO	3101+03.2			33	CENTERLINE
EQ STA 3101+03.02 (BK) = STA. 304+62.66 (AH)							
	304+62.7	TO	365+98.0			78	CENTERLINE
	365+98.0	TO	366+98.0			10	CENTERLINE
	366+98.0	TO	LT 374+78.0		36		MEDIAN
RT	373+78.0	TO	RT 374+78.0	4			LANE LINE
LT	375+73.0	TO	LT 376+73.0	4			
RT	375+73.0	TO	378+65.0		18		MEDIAN
SUBTOTAL LOCATION 2				8	54	167	
TOTAL LOCATION 2					229		
TOTALS AT US 51 LOCATION 2					722		

STATION TO STATION	RAISED REF PAVT MARKS	NOTES
	AMBER - TWO WAY FOOT	
IL 127 - STA. 335+53 TO STA. 227+32		
	12	Centerline
EQ STA 344+07.4 (BK.) = STA. 6+06.7 (AH.)		
	93	Centerline
EQ STA 79+77.7 (BK.) = STA. 80+07.7 (AH.)		
	75	Centerline
EQ STA 138+96.2 (BK.) = STA. 139+83.1 (AH.)		
	110	Centerline
TOTAL		290

PLOT DATE = 1/24/2008
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = mcorcoran