F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2744	06-00183-00-CH	COOK	73	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83999

SUMMARY OF QUANTITIES

	IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODES							
					I000-1A ROADWAY	Y030-1E LIGHTING	Y031-1F TRAFFIC SIGNALS					VILLAGE OF WILMETTE
					80% IDOT 20% WILMETTE	80% IDOT 20% WILMETTE	LAKE AVE 80% IDOT 20%WILMETTE	CENTRAL AVE 80% IDOT 20% WILMETTE	WILMETTE AVE 80% IDOT 20% WILMETTE	LINDEN AVE 80% IDOT 20% WILMETTE	INTERCONNECT 80% IDOT 20% WILMETTE	100% WILMETTE
*	20100110	TREE REMOVAL (6-15 UNIT DIAMETER)	UNIT	42	42							
*	20101000	TEMPORARY FENCE	FOOT	120	120							
*	20200100	EARTH EXCAVATION	CU YD	749	749							
*	20800150	TRENCH BACKFILL	CU YD	9	9							
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	198	198							
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3	3							
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3	3							
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	3							
*	25200110	SODDING, SALT TOLERANT	SQ YD	198	198							
*	25200200	SUPPLEMENTAL WATERING	UNIT	2.0	2.0							
*	28000510	INLET FILTERS	EACH	18	18							
*	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1288	1288							
*	35301400	PORTLAND CEMENT CONCRETE BASE COURSE (VARIABLE DEPTH)	SQ YD	810	810							
*	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.4	4.4							
*	40600300	AGGREGATE (PRIMECOAT)	TON	22	22							
*	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	234	234							
*	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	464	464							
*	42001300	PROTECTIVE COAT	SQ YD	1140	1140							
*	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	21	21							
*	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	174	174							
*	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQ FT	2830	2830							
*	42400800	DETECTABLE WARNINGS	SQ FT	112	112							
*	44000100	PAVEMENT REMOVAL	SQ YD	425	425							
*	44000158	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"	SQ YD	4852	4852							
*	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	366	366							
*	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1624	1624							
*	44000600	SIDEWALK REMOVAL	SQ FT	4109	4109							
*	44003100	MEDIAN REMOVAL	SQ FT	796	796							
*	44201474	CLASS C PATCHES, TYPE I	SQ YD	13	13							
*	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1450	1450							
*	550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2, 12"	FOOT	35	35							
*	55100500	STORM SEWER REMOVAL 12"	FOOT	20	20							
△ *	56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1	1							
*	60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	1	1							
*	60234200	INLETS, TYPE A, TYPE 1 FRAME OPEN LID	EACH	2	2							
*	60250200	CATCH BASINS TO BE ADJUSTED	EACH	11	11							
*	60255500	MANHOLES TO BE ADJUSTED	EACH	20	20							
*	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	6	6							
*	60260100	INLETS TO BE ADJUSTED	EACH	3	3							
*	60500060	REMOVING INLETS	EACH	2	2							
*	60600605	CONCRETE CURB, TYPE B	FOOT	215	215							

△ SPECIALTY ITEMS

PLAN	BY	DATE
SURVEYED		
PLOTTED		
ALIGNMENT CHECKED		
DRAWN BY		
CADD FILE NAME		
NOTE BOOK NO.		

PROFILE	BY	DATE
SURVEYED		
PLOTTED		
GRADES CHECKED		
DRAWN BY		
STRUCTURE NOTATNS CHKD		
NOTE BOOK NO.		

REVISIONS	
NAME	DATE

SUMMARY OF QUANTITIES

SHEET 1 OF 4

CONSULTANT

TYLIN INTERNATIONAL

VILLAGE OF WILMETTE
GREEN BAY ROAD
INTERSECTION IMPROVEMENTS

DRAWN: CBS	SHEET NO.
CHECKED:	
APPROVED:	
DATE: 02-14-2008	
SCALE: NONE	
JOB NO.:	PROJECT NO.: