

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2744	06-00183-00-CH	COOK	73	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 83999				

IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODES							VILLAGE OF WILMETTE 100% WILMETTE
				1000-1A ROADWAY	Y030-1E LIGHTING	Y031-1F TRAFFIC SIGNALS					
				80% IDOT 20% WILMETTE	80% IDOT 20% WILMETTE	LAKE AVE 80% IDOT 20% WILMETTE	CENTRAL AVE 80% IDOT 20% WILMETTE	WILMETTE AVE 80% IDOT 20% WILMETTE	LINDEN AVE 80% IDOT 20% WILMETTE	INTERCONNECT 80% IDOT 20% WILMETTE	
* 60601105	CONCRETE CURB, TYPE M	FOOT	315	315							
* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1414	1414							
* 60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	2105	2105							
* 60623711	CONCRETE MEDIAN	SQ FT	289	289							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6							
67100100	MOBILIZATION	L SUM	1	1							
* 70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1							
* 70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	-2	2							
* 70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3							
* 70300100	SHORT TERM PAVEMENT MARKING	FOOT	240	240							
* 70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS & SYMBOLS	SQ FT	109	109							
* 70300520	PAVEMENT MARKING TAPE, TYPE III - LINE 4"	FOOT	4502	4502							
* 70300560	PAVEMENT MARKING TAPE, TYPE III - LINE 12"	FOOT	51	51							
* 70300570	PAVEMENT MARKING TAPE, TYPE III - LINE 24"	FOOT	51	51							
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1763	1763							
* 72000100	SIGN PANEL - TYPE 1	SQ FT	275	275							
* 72400710	RELOCATE SIGN PANEL, TYPE 1	SQ FT	138	138							
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	105	105							
* 72900100	METAL POST, TYPE A	FOOT	41	41							
* 72900200	METAL POST, TYPE B	FOOT	46	46							
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	8	8							
Δ * 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	874	874							
Δ * 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3775	3775							
Δ * 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5637	5637							
Δ * 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	900	900							
Δ * 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	462	462							
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	3860	3860							
Δ XX006937	GROUND ROD, 5/8" DIAMETER x 10 FT.	EACH	6	6							
Δ 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	115		99	8	8				
Δ 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	54		50	4					
Δ 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	123	123							
Δ 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	38		38						
Δ 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	70		35		35				
Δ 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	62			62					
Δ 81019100	CONDUIT PUSHED, 6" DIA., GALVANIZED STEEL	FOOT	60		60						
Δ 81400100	HANDHOLE	EACH	5		2	2	1				
Δ 81400200	HEAVY-DUTY HANDHOLE	EACH	5		4		1				
Δ 81400300	DOUBLE HANDHOLE	EACH	1		1						
Δ 81603090	UNIT DUCT, 600V, 3-1/C NO. 4, 1/C NO. 6 GROUND (XLP TYPE USE), 1-1/4 INCH POLYETHYLENE	FOOT	200	200							
Δ 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	692	487	187	10	8				

Δ SPECIALTY ITEMS

PLAN
NO. _____
DATE _____
BY _____
REVISIONS
CHECKED _____
ALIGNMENT CHECKED _____
ELECTRIC CHECKED _____
CADD FILE NAME _____

PROFILE
NO. _____
DATE _____
BY _____
REVISIONS
CHECKED _____
GRADES CHECKED _____
STRUCTURE NOTATION CHECKED _____

REVISIONS	
NAME	DATE

SUMMARY OF QUANTITIES

SHEET 2 OF 4

CONSULTANT
TYLIN INTERNATIONAL

VILLAGE OF WILMETTE GREEN BAY ROAD INTERSECTION IMPROVEMENTS	
DRAWN: CBS	SHEET NO.
CHECKED:	
APPROVED:	
DATE: 02-14-2008	
SCALE: NONE	
JOB NO.:	PROJECT NO.: