

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6761	04-00057-06-WR	TAZEWELL	154	4
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES				TAZEWELL COUNTY 80% FEDERAL / 20% STATE CONSTRUCTION TYPE CODE	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000-2A	X028-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	24	24	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	90	90	
20100500	TREE REMOVAL, ACRES	ACRE	1.9	1.9	
20200100	EARTH EXCAVATION	CU YD	19,010	19,010	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,516	2,516	
20400100	BORROW EXCAVATION	CU YD	9,600	9,600	
20800150	TRENCH BACKFILL	CU YD	437	437	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,939	1,939	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	29,739	29,739	
* 25000110	SEEDING, CLASS 1A	ACRE	2.50	2.50	
* 25000210	SEEDING, CLASS 2A	ACRE	3.60	3.60	
* 25000322	SEEDING, CLASS 5A	ACRE	3.70	3.70	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	829	829	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	829	829	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	829	829	
* 25100115	MULCH, METHOD 2	ACRE	9.20	9.20	
25100630	EROSION CONTROL BLANKET	SQ YD	1,673	1,673	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	624	624	
28000300	TEMPORARY DITCH CHECKS	EACH	27	27	
28000310	AGGREGATE DITCH CHECKS	EACH	38	38	
28000400	PERIMETER EROSION BARRIER	FOOT	1,213	1,213	
28000500	INLET AND PIPE PROTECTION	EACH	52	52	
28100725	STONE DUMPED RIPRAP, CLASS B3	SQ YD	1,129	1,129	
X007355	STONE DUMPED RIPRAP, CLASS B4	SQ YD	1,544	1,544	
28200200	FILTER FABRIC	SQ YD	2,547	2,547	
28300400	AGGREGATE DITCH	TON	214	214	
28500100	FABRIC FORMED CONCRETE REVETMENT MATS	SQ YD	52	52	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	15,433	15,433	
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	568	568	
35501318	HOT-MIX ASPHALT BASE COURSE, 8 1/2"	SQ YD	14,358	14,358	
35600700	HOT-MIX ASPHALT BASE COURSE WIDENING 6"	SQ YD	242	242	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	99	99	
40300305	POLYMERIZED BITUMINOUS MATERIALS (COVERS AND SEAL COATS)	GAL	230	230	
40300500	COVER COAT AGGREGATE	TON	8	8	
40300600	SEAL COAT AGGREGATE	TON	4	4	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
BROADWAY ROAD IMPROVEMENTS
 SUMMARY OF QUANTITIES

SCALE: AS SHOWN
 DATE 12/07/2007
 DRAWN BY: DLC
 CHECKED BY: REW