

F.A.U. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6761 04-00057-06-WR	TAZEWELL	154	15
STA. TO STA.		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT	

TREE REMOVAL			
LOCATION			
		6 - 15 UNIT	OVER 15 UNIT
STA. 31+42.00	RT	12	
STA. 43+61.00	RT		36
STA. 43+74.00	RT		36
STA. 44+03.00	RT	12	
STA. 44+10.00	RT		18
TOTAL		24	90

TREE REMOVAL					
LOCATION					
					ACRES
STA. 52+62.00	RT	TO	STA. 55+00.00	RT	0.294
STA. 56+00.00	RT	TO	STA. 57+66.00	RT	0.240
STA. 58+65.00	LT	TO	STA. 59+55.00	LT	0.141
STA. 58+50.00	RT	TO	STA. 60+50.00	RT	0.275
STA. 65+20.00	LT	TO	STA. 67+00.00	LT	0.012
STA. 67+00.00	LT	TO	STA. 68+50.00	LT	0.112
STA. 71+75.00	LT	TO	STA. 73+00.00	LT	0.090
STA. 71+80.00	RT	TO	STA. 73+00.00	RT	0.048
STA. 73+00.00	RT	TO	STA. 76+15.00	RT	0.640
TOTAL					1.852

PAVEMENT REMOVAL SCHEDULE							
LOCATION							
						PAVEMENT REMOVAL SQ YD	DRIVEWAY PAVEMENT REMOVAL SQ YD
STA. 8+00.00	RT	TO	STA. 10+87.04	RT		66.00	
STA. 8+65.00	LT	TO	STA. 8+80.00	LT		8.00	
STA. 10+67.04	RT	TO	STA. 18+50.00	RT		1,452.68	
STA. 32+95.26	LT	TO	STA. 34+19.78	LT		32.28	
STA. 36+30.79	LT	TO	STA. 37+00.00	LT		20.67	
STA. 41+44.87	LT	TO	STA. 42+24.73	LT		159.35	
STA. 46+34.80	LT	TO	STA. 48+00.00	LT		451.10	
STA. 57+73.61	RT	TO	STA. 58+45.57	RT		53.37	
STA. 74+50.00	LT	TO	STA. 75+50.00	LT		133.33	
STA. 10+88.68	LT	TO	STA. 11+45.84	LT			168.87
STA. 15+86.40	LT	TO	STA. 16+31.09	LT			164.58
STA. 20+53.00	RT	TO	STA. 20+87.00	RT			53.00
STA. 22+40.43	RT	TO	STA. 22+67.94	RT			48.60
STA. 22+67.94	RT	TO	STA. 23+08.34	RT			68.73
STA. 24+03.66	RT	TO	STA. 24+46.80	RT			64.42
STA. 24+46.80	RT	TO	STA. 24+80.78	RT			68.87
STA. 25+85.60	RT	TO	STA. 26+25.08	RT			70.84
STA. 26+83.37	RT	TO	STA. 27+23.13	RT			43.58
STA. 28+28.04	LT	TO	STA. 28+88.02	LT			142.66
STA. 29+77.64	RT	TO	STA. 30+31.49	RT			66.32
STA. 30+86.83	LT	TO	STA. 31+43.79	LT			124.00
STA. 33+20.17	LT	TO	STA. 33+83.05	LT			90.76
STA. 35+19.68	LT	TO	STA. 35+57.70	LT			44.49
STA. 36+69.71	LT	TO	STA. 36+96.29	LT			34.80
STA. 38+12.73	LT	TO	STA. 38+45.00	LT			65.28
STA. 39+14.83	LT	TO	STA. 39+58.62	LT			60.69
STA. 43+83.94	LT	TO	STA. 44+10.08	LT			49.41
STA. 45+50.46	LT	TO	STA. 46+87.78	LT			56.31
STA. 46+01.26	LT	TO	STA. 46+32.22	LT			34.52
STA. 46+89.72	LT	TO	STA. 47+16.33	LT			32.14
STA. 48+08.76	LT	TO	STA. 48+92.50	LT			77.52
TOTAL						2,397	1,651

PIPE CULVERT REMOVAL						
LOCATION						
				SIZE	PIPE CULVERT REMOVAL FOOT	
STA. 10+75.00	LT	TO	STA. 11+48.00	15"	73	
STA. 15+67.00	LT	TO	STA. 16+31.00	15"	64	
STA. 18+68.00	LT	TO	STA. 19+48.00	15"	80	
STA. 22+42.00	RT	TO	STA. 22+68.00	15"	26	
STA. 22+97.00	RT	TO	STA. 22+72.00	15"	25	
STA. 24+19.00	RT	TO	STA. 24+92.00	15"	27	
STA. 24+92.00	RT	TO	STA. 24+47.00	15"	73	
STA. 25+21.00	LT	TO	STA. 26+09.00	RCP	88	
STA. 25+78.00	RT	TO	STA. 26+29.00	15"	51	
STA. 26+92.00	RT	TO	STA. 27+18.00	15"	26	
STA. 27+11.00	LT	TO	STA. 27+88.00	15"	77	
STA. 28+40.00	LT	TO	STA. 28+78.00	15"	38	
STA. 29+78.00	RT	TO	STA. 30+30.00	15"	52	
STA. 30+79.00	LT	TO	STA. 31+50.00	15"	71	
STA. 31+31.00	RT	TO	STA. 31+96.00	12"	65	
STA. 35+30.00	LT	TO	STA. 35+56.00	15"	26	
STA. 36+72.00	LT	TO	STA. 36+98.00	15"	26	
STA. 38+18.00	LT	TO	STA. 38+44.00	15"	26	
STA. 39+27.00	LT	TO	STA. 39+53.00	15"	26	
STA. 41+46.00	LT	TO	STA. 42+26.00	15"	80	
STA. 46+06.00	LT	TO	STA. 46+32.00	15"	26	
STA. 46+86.00	LT	TO	STA. 47+14.00	15"	26	
STA. 48+26.00	LT	TO	STA. 48+79.00	15"	50	
STA. 22+64.00	LT	TO	STA. 23+21.00	15"	57	
STA. 24+19.00	LT	TO	STA. 24+59.00	TBD	40	
STA. 49+93.00	LT	TO	STA. 51+13.00	15"	120	
STA. 60+85.00	RT	TO	STA. 61+10.00	15"	25	
TOTAL					1,362	

COMBINATION CURB AND GUTTER REMOVAL					
LOCATION					
				FT	
STA. 7+00.00	TO	STA. 10+85.00	RT	270	
STA. 8+59.00	TO	STA. 8+92.00	LT	40	
STA. 18+91.00	TO	STA. 19+18.00	LT	43	
STA. 22+55.00	TO	STA. 23+30.00	LT	120	
STA. 25+23.00	TO	STA. 26+04.00	LT	133	
STA. 41+41.00	TO	STA. 42+25.00	LT	87	
STA. 49+91.00	TO	STA. 50+99.00	LT	80	
STA. 75+55.00	TO	STA. 78+74.00	RT	316	
TOTAL					1089

CONCRETE HEADWALL REMOVAL		
LOCATION		
		EACH
STA. 38+18.00	LT	1
STA. 38+44.00	LT	1
STA. 39+27.00	LT	1
STA. 39+53.00	LT	1
TOTAL		4

PAVEMENT MARKING REMOVAL SCHEDULE						
LOCATION						
			SOLID 4"	SOLID 8"	SOLID 12"	ARROWS
			SQ FT	SQ FT	SQ FT	SQ FT
RT. STA. 1+00						54.2
RT. STA. 1+50						27.1
RT. STA. 3+00						27.1
RT. STA. 3+80						27.1
RT. STA. 4+20	TO	LT. STA. 6+00	118.8			
RT. STA. 4+20	TO	RT. STA. 8+00		253.3		
RT. STA. 5+00						27.1
LT. STA. 6+00	TO	LT. STA. 8+00	132.0			
RT. STA. 6+00	TO	RT. STA. 8+00	66.0		62.5	
RT. STA. 6+40						27.1
RT. STA. 7+30						27.1
RT. STA. 8+00	TO	RT. STA. 10+88.5	88.6		143.9	
RT. STA. 9+00	TO	LT. STA. 34+00				208.2
RT. STA. 10+88.5	TO	RT. STA. 12+10	46.7			
LT. STA. 34+00	TO	LT. STA. 75+50				342.4
LT. STA. 76+25	TO	LT. STA. 78+00	115.5			
LT. STA. 76+25	TO	LT. STA. 80+30			88.0	
LT. STA. 76+85	TO	LT. STA. 80+30	227.7			
SUBTOTAL			785.3	253.3	284.4	216.8
TOTAL			2,108			

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL							
LOCATION							
				EST. DEPTH	EST. WIDTH	CU YD	REPLACEMENT MATERIAL
BROADWAY ROAD							
STA. 11+50	LT	TO	STA. 13+00	1.5'	4'	34	EMBANKMENT
STA. 12+00	LT	TO	STA. 30+00	1.0'	12'	800	EMBANKMENT
STA. 31+00	RT	TO	STA. 53+00	1.0'	12'	978	EMBANKMENT
STA. 64+00	LT	TO	STA. 67+00	1.0'	12'	133	EMBANKMENT
STA. 53+25	LT	TO	STA. 54+75	2.0'	6'	67	EMBANKMENT
STA. 59+98	LT			1.0'	4'	6	EMBANKMENT
STA. 59+80	RT			1'	5'	12	EMBANKMENT
STA. 73+00	LT			2' TO 5'		104	ROCKFILL
STA. 73+75	RT			3' TO 7'		382	ROCKFILL
TOTAL						2,516	

TOPSOIL EXCAVATION AND PLACEMENT						
LOCATION						
				EST. DEPTH	AVG. WIDTH	CU YD
BROADWAY ROAD						
STA. 14+50	LT	TO	STA. 22+80	1	25	525
STA. 32+00	RT	TO	STA. 41+00	1	32.4	756
STA. 44+00	LT	TO	STA. 52+00	1	31.7	658
TOTAL						1,939

GUARDRAIL AGGREGATE EROSION CONTROL				
LOCATION				
				TON
STA. 56+62.50	TO	STA. 60+25.00	LT	71.0
STA. 65+07.50	TO	STA. 72+32.50	LT	140.7
STA. 71+00.00	TO	STA. 75+50.00	RT	87.7
STA. 72+66.00	TO	STA. 75+52.50	LT	56.7
TOTAL				356.1

EARTH EXCAVATION							
LOCATION							
				CUT	FILL	BORROW EXCAVATION CU YD	
BROADWAY ROAD							
STA. 8+00	LT	TO	STA. 33+00	2,063	4,267	2,204	
STA. 33+00	LT	TO	STA. 58+00	573	3,477	2,904	
STA. 58+00	LT	TO	STA. 78+00	1,037	6,305	5,268	
STA. 8+00	RT	TO	STA. 33+00	1,800	958	-541	
STA. 33+00	RT	TO	STA. 58+00	10,691	6,856	-4,035	
STA. 58+00	RT	TO	STA. 78+00	3,146	6,944	3,788	
TOTAL				19,010	28,608	9,600	

FURNISH AND PLACE TOPSOIL, 4"	
LOCATION	SQ YD
BROADWAY ROAD	28,738
JOBSITE	
TOTAL	28,738

REVISIONS	
NAME	DATE
	1/16/07

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**BROADWAY ROAD IMPROVEMENTS  
 SCHEDULE OF QUANTITIES**

DRAWN BY: DLC  
 CHECKED BY: REW

DATE: 12/07/2007

PLT DATE = 2/11/2008  
 FILE NAME = I:\2008\BROADWAY\ANS\SCHED OF QTY-81.dgn  
 PLOT SCALE = 2.0000  
 USER NAME = DDOT