ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 11	*	EDGAR	160	4
FED.ROAD DIST.NO. 5	ILLINOIS	PROJECT		

* 05-00092-01-PV

SUMMARY OF QUANTITIES

	CODE NUMBER	DESCRIPTION	UNITS	80% FED 20% LOCAL 1000-2A QUANTITY
	542D0226	PIPE CULVERTS, CLASS D, TYPE 1, 21"	FOOT	36
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"	EACH	12
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTION 24"	EACH	2
	54213675	PRECAST REINFORCED CONCRETE FLARED END SECTION 30"	EACH	2
	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTION 36"	EACH	2
	54213693	PRECAST REINFORCED CONCRETE FLARED END SECTION 48"	EACH	2
	61100605	MISCELLANEOUS CONCRETE	CU YD	4
•	61101009	STORM SEWER PROTECTED, CLASS A, 8"	FOOT	258
•	61101011	STORM SEWER PROTECTED, CLASS A, 10"	FOOT	88
•	61101013	STORM SEWER PROTECTED, CLASS A, 12"	FOOT	90
•	61101020	STORM SEWER PROTECTED, CLASS A, 18"	FOOT	280
•	61101026	STORM SEWER PROTECTED, CLASS A, 24"	FOOT	187
Δ	63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES △1	FOOT	25
Δ •	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2
Δ	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	2
	63500205	REMOVE AND REPLACE DELINEATORS	EACH	14
	66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	97
	67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	5
	67100100	MOBILIZATION	L SUM	1
•	67201000	SEALING ABANDONED WATER WELLS	EACH	1
	70101860	TRAFFIC CONTROL AND PROTECTION STANDARD BLR 22 (SPECIAL)	L SUM	1
	72000100	SIGN PANEL, TYPE 1	SQ FT	32
	72900200	METAL POST, TYPE B	FOOT	58
Δ	78008210	POLYUREA PAVEMENT MARKING TYPE 1 LINE 4"	FOOT	33,910
Δ	78008270	POLYUREA PAVEMENT MARKING TYPE 1 LINE 24"	FOOT	132
Δ	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	184
	X0301232	SURVEY MARKER VAULTS	EACH	5
	X0974300	SIGN REMOVAL	EACH	5
	XX001017	REMOVE RIGHT-OF-WAY MARKERS	EACH	1
	XX002957	REMOVE AND RE-ERECT EXISTING SIGN	EACH	9
	XX003949	CONSTRUCTION STAKING	L SUM	1
	Z0030900	INSPECTION WELLS	EACH	16

Revised 4-3-08 △1

• SEE SPECIAL PROVISIONS
Δ SPECIALTY ITEMS

SUMMARY OF QUANTITIES

REVISIONS		
No.	DATE	INITIALS
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		

SHILOH ROAD (CH 11)
EDGAR COUNTY, ILLINOIS

HOMER L. CHASTAIN & ASSOCIATES, LLP
CONSULTING ENGINEERS
184-001397
DECATUR (217) 422-8544 CHICAGO (773) 714-0050
ROCKFORD (815) 489-0050

DRAWN BY	DATE RLK 7/07
CHECKED BY	DATE CAS 7/07
BOOK NUMBER	469
PROJECT No.	5245
SHEET No.	