

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
I-57	00-00374-03-LS	CHAMPAIGN	21	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 91382				

ITEM NUMBER	PAY ITEM	CONSTRUCTION CODE	TOTAL QUANTITY	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	970	
25000210	SEEDING, CLASS 2A	ACRE	0.2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	
25100105	MULCH METHOD 1	ACRE	0.2	
• 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	217	
25200200	SUPPLEMENTAL WATERING	UNIT	10	
50200100	STRUCTURE EXCAVATION	CU YD	121	
50300225	CONCRETE STRUCTURES	CU YD	155.6	
• 50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10820	
• 50901755	PARAPET RAILING, SPECIAL	FOOT	539	
51201400	FURNISHING STEEL PILES HP10X42	FOOT	833	
51202305	DRIVING PILES	FOOT	833	
51203400	TEST PILE STEEL HP10X42	EACH	3	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1	
• 63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	1	
67100100	MOBILIZATION	L SUM	1	
• 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	
• 80400100 ⁵	ELECTRIC SERVICE INSTALLATION, SPECIAL	L SUM EACH	1	⚠
81012200	CONDUIT IN TRENCH, 3/4" DIA., PVC	FOOT	354 317	⚠
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	108 205	⚠
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	100 160	⚠
81300800	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" x 12" x 6"	EACH	1	
81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	1	⚠
81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	700	
81702450	ELECTRICAL CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3 1/C ^{NO.} X10	FOOT	1254 1252	⚠
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1161 1171	⚠
82500510	LIGHTING CONTROLLER TYPE CB-RCS 60 AMP-240 VOLT	EACH	1	
• A2002420	TREE, BETULA NIGRA HERITAGE (HERITAGE RIVER BIRCH), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	12	
• D2015401	SHRUB, JUNIPERUS CHINENSIS 'KALLAY'S COMPACTA' (KALLAY COMPACT JUNIPER), 5 GALLON	EACH	84	
• X0325403	CONDUIT, FLEXIBLE NON-METALLIC, WEATHERPROOF, 2"	EACH	4	
• XX005856	MULCH - SHREDDED HARDWOOD BARK, 3" DEPTH	CU YD	40	
• XX006302	NEPETA X FAASSENII 'WALKERS LOW' (WALKERS LOW CATMINT)	EACH	1000	
• Z0013798	CONSTRUCTION LAYOUT	L SUM	1	
• Z0076600	TRAINEES	HOUR		
• 5000839	PERENNIAL, FALLOPIA JAPONICA 'COMPACTA' (COMPACT FLEECE FLOWER), 1 GALLON	EACH	3480	
• 5000840	PERENNIAL, MISCANTHUS SINENSIS 'PURPURASCENS' (PURPLE SILVER GRASS), 2 GALLON	EACH	40	

ITEM NUMBER	PAY ITEM	CONSTRUCTION CODE	TOTAL QUANTITY	
X8250500	• 5000841 LIGHTING UNIT X COMPLETE, SPECIAL		6	⚠
X0324390	• 5000842 FLOOD LIGHTING UNIT B, COMPLETE		6	⚠
• 5000843	MASONRY COLUMN, LARGE		2	
• 5000844	MASONRY COLUMN, SMALL		4	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411		2	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	
81018100	CONDUIT PUSHED, 3/4" DIA., GALVANIZED STEEL	FOOT	120	⚠

P:\101359\plans\Summary of Quantities.dgn 3/24/2008

Revised 3/28/08

• SEE SPECIAL PROVISIONS



REVISIONS	
NAME	DATE
RLH	3/18/08

DESIGN FIRM REGISTRATION
 No. 184-000480
 118 SOUTH CLINTON STREET
 SUITE 300
 CHICAGO, IL 60661
 PHONE : 312.848.9900
 FAX : 312.848.0204

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: As Noted
DATE: 01/04/08

DRAWN BY SLD
CHECKED BY JTP