

SCHEDULES OF QUANTITIES

LIGHTING SCHEDULE

LOCATION	LIGHTING UNIT-A COMPLETE, SPECIAL X8250500 (EACH)	FLOOD LIGHTING UNIT-B COMPLETE, X0324390 (EACH)	CONDUIT, FLEX. NON-METALLIC, WEATHERPRF, 2" (EACH)	CONDUIT IN TRENCH, 3/4" DIA. PVC (FOOT)	CONDUIT IN TRENCH, 2" DIA. PVC (FOOT)	CONDUIT PUSHED, 2" DIA. PVC (FOOT)	CONDUIT PUSHED, 3/4" DIA. GALVANIZED STEEL (FOOT)	JUNCTION BOX, 18" X 12" X 6" (EACH)	HANDHOLE, COMPOSITE CONCRETE (EACH)	TRENCH AND BACKFILL FOR ELECTRICAL WORK (FOOT)	UNIT DUCT (FOOT)	ELEC. CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3 1/2" X 10 NO. (FOOT)	ELEC. SERVICE INSTALLATION, SPECIAL (EACH)	LIGHTING CONTROLLER TYPE CB-RCS 60 AMP - 240 VOLT (EACH)
CURTIS 29+25RT	1	1												
CURTIS 29+25LT	1	1												
CURTIS 28+20RT	1	1		2.0					1					
CURTIS 28+20LT	1	1												
CURTIS 27+15RT	1	1												
CURTIS 27+15LT	1	1												
CURTIS 29+53LT			1		8.0					8.0				
CURTIS 29+53RT			1					1						
CURTIS 26+87LT			1											
CURTIS 26+87RT			1											
CURTIS 29+89LT TO 29+89RT						100.0						100.0		
CURTIS 29+53RT TO 29+89RT					50.0					50.0		50.0		
CURTIS 29+53LT TO 29+89LT					50.0					50.0		50.0		
CURTIS 29+53RT TO 35+60RT										700.0	700.0			
CURTIS 29+53RT TO 26+87RT												280.0		
CURTIS 29+53LT TO 26+87LT												280.0		
CURTIS 29+53RT TO 29+25LT				40.0						40.0		45.0		
CURTIS 29+53LT TO 29+25LT				50.0 40.0						50.0 40.0		45.0		
CURTIS 26+87RT TO 27+15RT				40.0						40.0		45.0		
CURTIS 26+87LT TO 27+15LT				40.0						40.0		45.0		
CURTIS 29+53RT TO 28+96RT				80.0	80.0					80.0		72.0		
CURTIS 28+96RT TO 28+36RT						60.0	60.0					60.0		
CURTIS 28+36RT TO 28+20RT				17.0	17.0					16.0 17.0		20.0		
CURTIS 28+20RT TO 28+20LT				145.0						145.0		150.0		
CURTIS 35+65RT													1	1
CURTIS 28+20LT TO 29+25LT				97.0						97.0		102.0		
CURTIS 28+96LT TO 28+36LT							60.0					60.0		
TOTALS	6	6	4	354.0	108.0	100.0	120.0	1	1	1161.0	700.0	1254.0	1	1
UNIT (EACH)	6	6	4	317.0	205.0	160.0	120.0	1	1	1171.0	700.0	1252.0	1	1
PAY ITEM	X8250500	X0324390	X0325403	81012200	81012600	81021330	81018100	81300800	81400730	81900200	81603035	81702450	80400105	82500510

p:\0328\plans\sheet\lighting_sheets.dgn 3/24/2008

Revised 3/22/08

DESIGN FIRM REGISTRATION
No. 164-000450
118 SOUTH CLINTON STREET
SUITE 800
CHICAGO, IL 60661
PHONE : 312.648.9800
FAX : 312.648.0204

REVISIONS	
RLH	DATE
	3/18/08

ILLINOIS DEPARTMENT OF TRANSPORTATION

LIGHTING SCHEDULE OF QUANTITIES

SCALE: As Noted
DATE: 01/04/08

DRAWN BY RS
CHECKED BY MTP