CONTRACT NO. 93454

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	99-P4003-01-BT	ADAMS	92	6
STA.		TO STA.		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	PARTICIPATING CONSTRUCTION TYPE CODE Y047			NON-PART.				
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"		FOOT	54	54							
* 78202000	TERMINAL MARKER - POST MOUNTED	Y	EACH	2	2							
* 80400100	ELECTRIC SERVICE INSTALLATION		EACH	1	1							
* 81000400	CONDUIT IN TRENCH, 1 1/4" DIA., GALVANIZED STEEL		FOOT	60	60							
* 81100400	CONDUIT ATTACHED TO STRUCTURE, 1 1/4" DIA., GALVANIZED STEEL		FOOT	140	140							
* 81300200	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 4" X 3"		EACH	3	3							
* 81700325	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 8		FOOT	270	270							
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK		FOOT	60	60							
* 82500530	LIGHTING CONTROLLER TYPE CB-RCS 100AMP - 240VOLT		EACH	1	1							
* 87800100	CONCRETE FOUNDATION, TYPE A		FOOT	3.0	3.0							
* XX007299	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR, VANDALPROOF	Y	EACH	3	3							

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

SUMMARY OF QUANTITIES
SHEET 4 OF 4

99-P4003-01-BT
QUINCY PARK DISTRICT, ADAMS COUNTY

SCALE: VERT. HORIZ. NONE
DRAWN BY SEB
DATE 2/1/2008
CHECKED BY DCD

PLOT DATE = 2/4/2008
FILE NAME = P:\SAFILES\ALSOM\94_SOM_13\CONST_PLANS\00PSBLM_04_SH_SOM_13.DGN
PLOT SCALE = 20.0000 ' / IN.
USER NAME = SEB