

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	99-P4003-01-BT	ADAMS	92	11
STA.			TO STA.	

PAVEMENT MARKING SCHEDULE

TRAIL	STATION TO STATION	SIDE	7800110		7800180	7800350	
			PAINT PAVEMENT MARKING - LINE				PREF PL PM
			4"	24"	WHITE SOLID	WHITE SOLID	TYPE B LINE 12"
			YELLOW SOLID	WHITE SOLID	WHITE SOLID	WHITE SOLID	
			FOOT	FOOT	FOOT	FOOT	
CEDAR CREEK TRAIL	99+80 TO 105+50	CL	570				
		RT		384			
	105+50 TO 106+76	CL	126				
	107+58 TO 111+50	CL	392				
	111+50 TO 115+14	CL	364				
	115+95 TO 117+50	CL	155				
12TH ST SPUR	500+11 TO 502+17	LT			8		
		CL	206				
		RT		5			
MAYS PARK SPUR	60+12 TO 60+50	LT			8		
		CL	38				
	60+50 TO 66+00	CL	550				
	66+00 TO 72+00	CL	600				
NORTH 12TH STREET	CROSSWALK					54	
			4193	384			
SUB TOTAL:							
TOTALS:			4577	21	54		

DRAINAGE SCHEDULE

PLAN LABEL	TRAIL	STATION	20800150	542C0223	542C1063	54223495	54213453	54213663	550A0090	60238305
			TRENCH BACKFILL	PIPE CULVERTS, CLASS C, TYPE 1 18"	PIPE CULVERTS, CLASS C, TYPE 2 18"	REMOVE AND RELAY PIPE CULVERTS 60"	END SECTIONS 18"	PRECAST REINF CONC FLARED END SECTIONS 18"	STORM SEWERS, CLASS A, TYPE 1 18"	INLETS, TYPE A, WITH MEDIAN INLET (604101)
			CU YD	FOOT	FOOT	FOOT	EACH	FOOT	FOOT	EACH
1	CEDAR CREEK	101+00	1.8					1	32.0	2
2	CEDAR CREEK	102+75	1.8					1	30.0	1
3	CEDAR CREEK	104+50	2.7		38.0		2			
4	12TH ST BYPASS	7+81	3.5		40.0		2			
5	CEDAR CREEK	109+75	2.2	35.0			2			
6	CEDAR CREEK	118+50	2.2	25.0			2			
7	CEDAR CREEK	124+50	2.2	26.0			2			
8	12TH ST BYPASS	5+25	1.5	22.0			2			
9	MAYS PARK SPUR	61+00	2.2	36.0			2			
10	MAYS PARK SPUR	66+75	10.7			45.0				
TOTALS:			31	144	78	45	14	2	62	3

FENCE SCHEDULE

LOCATION		66400305	66407800	XX000503
		CHAIN LINK FENCE, 6'	CHAIN LINK GATES, 6' X 16' DOUBLE	SPLIT RAIL FENCE
		FOOT	EACH	FOOT
12TH STREET SPUR	501+86.5 34.0' LT TO 400' WEST			400.0
12TH STREET BYPASS SW	2+08.0 5.0' RT TO 3+82.7 18.7' RT	180.0		
	3+82.7 18.7' RT TO 3+92.1 17.6' RT	9.4		
	4+00.0 16.8' RT		1	
	4+08.0 15.9' RT TO 4+16.2 15.0' RT	8.3		
	4+16.2 15.0' RT TO 6+11.7 24.0' RT	190.0		
TOTALS:		388	1	400

CURB & GUTTER SCHEDULE

LOCATION	60603800
	COMBINATION CURB AND GUTTER TYPE B-6.12
	FOOT
NORTH 12TH STREET NORTHEAST OF BRIDGE	16.0
TOTALS:	16

MISCELLANEOUS ITEMS SCHEDULE

LOCATION		XX001011	XX001683
		BICYCLE RACKS	INFORMATION KIOSK
		EACH	EACH
CEDAR CREEK TRAIL	100+22.0 LT	4	
	100+35.5 LT		1
MAYS PARK SPUR	74+36.0 LT		1
	74+48.5 LT	4	
TOTALS:		8	2

RAILING SCHEDULE

LOCATION			50900810	50901720
			PEDESTRIAN RAIL (SPECIAL)	BICYCLE RAILING
			FOOT	FOOT
SN 001-7004	WEST ABUTMENT	LT	12.0	
		RT	12.0	
	EAST ABUTMENT	LT	12.0	
		RT	12.0	
SN 001-7005	WEST ABUTMENT	LT	12.0	
		RT	12.0	
	EAST ABUTMENT	LT	12.0	
		RT	12.0	
12TH STREET BYPASS SW	1+12.5 TO 1+28.6 LT			19.0
	1+28.8 TO 1+67.8 LT			40.0
TOTALS:			96	59

SEGMENTAL CONCRETE BLOCK WALL SCHEDULE

LOCATION	X0322923
	SEGMENTAL CONCRETE BLOCK WALL
	SQ FT
CEDAR CREEK TRAIL 114+25.0 TO 115+02.0 RT	233
TOTALS:	233

REVISIONS	
NAME	DATE

SCHEDULE OF QUANTITIES
SHEET 4 OF 4

99-P4003-01-BT
QUINCY PARK DISTRICT, ADAMS COUNTY

SCALE: VERT. NONE
HORIZ. NONE

DATE: 2/11/2008

DRAWN BY: SEB
CHECKED BY: DCD