

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	00-00127-00-WR	COLES	91	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	IL 121	C.H. 18	TOTAL
* 20200100	EARTH EXCAVATION	CU YD	2080	13662	15742
* 20200500	EARTH EXCAVATION (WIDENING)	CU YD	99	514	613
20400800	FURNISHED EXCAVATION	CU YD	0	199	199
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	0	1622	1622
21301052	EXPLORATION TRENCH 52" DEPTH	FEET	305	3765	4070
* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.8	16.1	17.9
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	180	1610	1790
28000300	TEMPORARY DITCH CHECKS	EACH	8	47	55
28000400	PERIMETER EROSION BARRIER	FEET	0	2231	2231
28000500	INLET AND PIPE PROTECTION	EACH	3	19	22
28100107	STONE RIPRAP, CLASS A4	SQ YD	0	8	8
28200200	FILTER FABRIC	SQ YD	0	8	8
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	886	7066	7952
30201500	LIME	TONS	20	159	179
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TONS	252	151	403
35101400	AGGREGATE BASE COURSE, TYPE B	TONS	9	0	9
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	0	345	345
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	313	0	313
* 40200800	AGGREGATE SURFACE COURSE, TYPE B	TONS	37	316	353
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLONS	2293	22	2315
40600300	AGGREGATE (PRIME COAT)	TONS	15	0.4	15
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	231	0	231
40600990	TEMPORARY RAMP	SQ YD	48	13	61
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TONS	966	0	966
40603100	HOT-MIX ASPHALT BINDER COURSE, IL-19.0L, N30	TONS	1741	0	1741

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	IL 121	C.H. 18	TOTAL
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TONS	659	18	677
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLONS	9	0	9
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TONS	5	0	5
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	0	66	66
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	819	6335	7154
42001300	PROTECTIVE COAT	SQ YD	926	6362	7288
* 42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	0	487	487
44000100	PAVEMENT REMOVAL	SQ YD	439	0	439
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	0	213	213
* 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	0	1801	1801
44000400	GUTTER REMOVAL	FEET	0	60	60
44004250	PAVED SHOULDER REMOVAL	SQ YD	548	0	548
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SQ YD	91	0	91
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FEET	922	0	922
48101200	AGGREGATE SHOULDERS, TYPE B	TONS	514.5	1543.5	2058
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1115	0	1115
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	0	1	1
* 50104600	CONCRETE RETAINING WALL REMOVAL	FEET	0	30	30
50105200	REMOVE EXISTING CULVERTS	EACH	3	17	20
50800205	REINFORCEMENT BARS, EPOXY COATED	LBS	228.3	3295.4	3524

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY SJF
 HORIZ. CHECKED BY MED
 DATE 02/29/2008

TUC PROJ. #3103027
 ...\\IT\TOPPING\SHEET.dgn