

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	00-00127-00-WR	COLES	91	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	IL 121	C.H. 18	TOTAL
54001000	BOX CULVERT END SECTIONS	EACH	2	0	2
54010503	PRECAST CONCRETE BOX CULVERT 5X3'	FEET	61	0	61
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FEET	0	8	8
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FEET	0	80	80
54200451	PIPE CULVERTS, TYPE 1 RCCP 36"	FEET	160	0	160
54200463	PIPE CULVERTS, TYPE 1 RCCP 48"	FEET	104	0	104
54200637	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 12"	FEET	0	30	30
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FEET	0	330	330
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FEET	0	126	126
* 54205050	PIPE CULVERTS, SPECIAL 15"	FEET	0	50	50
54207171	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	FEET	0	180	180
54207177	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 42"	FEET	0	45	45
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	0	2	2
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	0	4	4
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4	0	4
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	0	2
54214731	PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	EACH	0	8	8
54214737	PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ELLIPTICAL, EQUIVALENT ROUND-SIZE 42"	EACH	0	2	2
54215550	METAL END SECTIONS 15"	EACH	0	2	2
54215553	METAL END SECTIONS 18"	EACH	0	4	4
54217722	REINFORCED CONCRETE PIPE TEE, 48" PIPE WITH 24" RISER	EACH	1	0	1
54244405	FLUSH INLET BOX FOR MEDIAN, STD 542546	EACH	0	1	1
* 54248160	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 36"	EACH	0	8	8
* 54248170	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 42"	EACH	0	2	2
54248510	CONCRETE COLLAR	CU YD	0	1.5	1.5

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	IL 121	C.H. 18	TOTAL
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FEET	8	0	8
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FEET	97	0	97
550B0010	STORM SEWERS, CLASS B, TYPE 1 4"	FEET	0	80	80
550B0020	STORM SEWERS, CLASS B, TYPE 1 6"	FEET	0	80	80
550B0030	STORM SEWERS, CLASS B, TYPE 1 8"	FEET	0	80	80
550B0300	STORM SEWERS, CLASS B, TYPE 2 4"	FEET	0	80	80
550B0310	STORM SEWERS, CLASS B, TYPE 2 6"	FEET	0	80	80
550B0320	STORM SEWERS, CLASS B, TYPE 2 8"	FEET	0	80	80
550B0360	STORM SEWERS, CLASS B, TYPE 2 15"	FEET	0	210	210
55100500	STORM SEWER REMOVAL 12"	FEET	97	0	97
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	60	74	134
60235300	INLETS, TYPE A, WITH TYPE 1 FRAME, CLOSED LID	EACH	1	0	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	0	1
* 60242400	INLETS, SPECIAL	EACH	0	1	1
60500060	REMOVING INLETS	EACH	1	0	1
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	0	1	1
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	10.5	0	10.5
60602800	CONCRETE GUTTER, TYPE B	FEET	0	137	137
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FEET	250	0	250
61100605	MISCELLANEOUS CONCRETE	CU YD	0	1.5	1.5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 02/29/2008

DRAWN BY SJF
CHECKED BY MED

TUG PROJ. #3103027
...\\white\topping\sheet\lgdn