

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	00-00127-00-WR	COLES	91	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

## SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	IL 121	C.H. 18	TOTAL
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	1	25	26
67100100	MOBILIZATION	L SUM	0.26	0.74	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	10	0	10
70300100	SHORT-TERM PAVEMENT MARKING	FEET	4661	0	4661
70300200	TEMPORARY PAVEMENT MARKING	FEET	10391	0	10391
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1554	0	1554
72000100	SIGN PANEL-TYPE 1	SQ FT	0	114	114
* 72000105	SIGN PANEL-TYPE 1 (SPECIAL)	SQ FT	0	13	13
72800100	TELESCOPING STEEL SIGN SUPPORT	FEET	0	294	294
△ 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	156	0	156
△ 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FEET	9752	0	9752
△ 78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FEET	540	0	540
△ 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FEET	197	0	197
△ 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FEET	32	0	32
△ 78001110	PAINT PAVEMENT MARKING-LINE 4"	FEET	0	21598	21598
△ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	112	0	112
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	59	0	59
* X4200755	PORTLAND CEMENT CONCRETE OVERLAY, 5 1/2"	SQ YD	0	15623	15623
* X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	2	5	7
* XX004646	ENGINEERED FILL, CLASS 4	CU YD	146	0	146
* XX005699	BITUMINOUS SURFACE TREATMENT, A-3 SPECIAL	SQ YD	0	345	345
* XX007218	PORTLAND CEMENT CONCRETE PAVEMENT 9" (WIDENING)	SQ YD	0	5756	5756

△ SPECIALTY ITEMS

## SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	IL 121	C.H. 18	TOTAL
* Z0013798	CONSTRUCTION LAYOUT	L SUM	0.26	0.74	1
* Z0030900	INSPECTION WELLS	EACH	1	8	9
Z0048665	RR LIABILITY & PROTECTION INSURANCE	L SUM	0	1	1
* Z0055300	RUMBLE STRIP	EACH	0	3	3

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SUMMARY OF QUANTITIES

SCALE: VERT.  
HORIZ.  
DATE 02/29/2008

DRAWN BY SJF  
CHECKED BY MED

TUG PROJ. #3103027  
...\\ntre\topping\sheet1.dgn