

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	00-00127-00-WR	COLES	91	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAVING SCHEDULE, STATION 20+90 TO STATION 46+35.29

	PROCESSING MODIFIED SOIL 12" SQ YD	LIME TONS	SUB-BASE GRANULAR MATERIAL TYPE B TONS	AGGREGATE BASE COURSE TY A, 8" SQ YD	P.C.C. PAVEMENT JOINTED, 8" SQ YD	PROTECTIVE COAT SQ YD	AGGREGATE SHOULDERS TYPE B TONS	HOT-MIX ASPHALT SHOULDERS 8" SQ YD	REINFORCEMENT BARS, EPOXY COATED LBS	BIT. SURFACE TREATMENT, A-3 SPECIAL SQ YD	HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50 TONS	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TONS	HOT-MIX ASPHALT BINDER COURSE IL 19.0L N30 TONS	HOT-MIX ASPHALT BINDER COURSE IL 19.0 N50 TONS	HOT-MIX ASPHALT BASE COURSE, WIDENING 9" SQ YD	
IL 121																	
533+24.36 TO 539+30.00			142.6				193.5	407.3			212.3	758.7	5.1	595.7	334.0	161.6	
539+30.00 TO 545+40.00			109.6				137.4	304.9			205.1	672.0	4.5	1071.1	547.8	151.1	
545+40.00 TO 551+44.36							183.6	403.0			197.9	665.7	4.4	6.9	83.9		
C. H. 18																	
20+90.00 TO 26+00.00	1,393.9	31.4			1,274.0	1,408.0	38.4		466.0		61.1	218.4	1.4	66.9			
26+00.00 TO 31+50.00	1,772.2	39.8			1,588.9	1,588.9	93.8		826.1								
31+50.00 TO 37+30.00	1,868.9	42.1			1,675.6	1,675.6	95.2		871.2								
37+30.00 TO 43+10.00	1,868.9	42.1			1,675.6	1,675.6	99.1		871.2								
43+10.00 TO 46+35.29	1,048.1	23.5			939.7	939.7	55.6		489.2								
FRONTAGE ROAD																	
10+00.00 TO 11+95.11				345.3			33.4			345.3							
TOTALS	7,952.0	178.9	252.2	345.3	7,153.8	7,287.8	930.0	1,115.2	3,523.7	345.3	676.4	2314.8	15.4	1740.6	965.7	312.7	

EARTHWORK SCHEDULE

	EARTH EXCAVATION (WIDENING) CU YD	EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) CU YD	EMBANKMENT CU YD	FURNISHED EXCAVATION OR WASTE (-) CU YD	SEEDING CLASS II SPECIAL ACRE	TOPSOIL FURNISH AND PLACE 6" SQ YD
IL 121							
533+24.36 TO 539+30.00	80.2	415.2	371.5	222.3	-149.2	0.42	
539+30.00 TO 545+40.00	19.3	828.1	635.5	509.0	-126.5	0.73	
545+40.00 TO 551+44.36		836.3	627.2	262.2	-365.0	0.63	
C. H. 18							
20+90.00 TO 26+00.00		559.1	419.3	1229.7	810.4	0.40	
26+00.00 TO 31+50.00		752.2	564.1	1532.1	967.9	0.58	
31+50.00 TO 37+30.00		295.9	221.9	2007.4	1785.5	0.49	
37+30.00 TO 43+10.00		446.8	335.1	1103.7	768.6	0.52	
43+10.00 TO 46+35.29		172.2	129.2	162.4	33.2	0.25	
46+00.00 TO 50+00.00		654.0	490.5	230.0	-260.5		
50+00.00 TO 55+00.00		768.0	576.0	303.0	-273.0		
55+00.00 TO 60+00.00		888.0	666.0	284.0	-382.0		
60+00.00 TO 65+00.00		628.0	471.0	316.0	-155.0		
65+00.00 TO 70+00.00		548.0	411.0	352.0	-59.0		
70+00.00 TO 75+00.00		778.0	583.5	242.0	-341.5		
75+00.00 TO 80+00.00		547.0	410.3	331.0	-79.3		
80+00.00 TO 85+00.00		471.0	353.3	441.0	87.8	8.60	
85+00.00 TO 90+00.00		634.0	475.5	370.0	-105.5		
90+00.00 TO 95+00.00		779.0	584.3	408.0	-176.3		
95+00.00 TO 100+00.00		654.0	490.5	441.0	-49.5		
100+00.00 TO 105+00.00		556.0	417.0	389.0	-28.0		
105+00.00 TO 110+00.00		716.0	537.0	311.0	-226.0		
110+00.00 TO 115+00.00		975.0	731.3	382.0	-349.3		
115+00.00 TO 120+00.00		638.0	478.5	384.0	-94.5		
46+00.00 TO 120+00.00	514.0		385.5		385.5		
TR 14							
42+50 TO 43+00		9.0	6.8	0.0	-6.8		
TR 14A							
50+00 TO 50+50		8.0	6.0	0.0	-6.0		
FRONTAGE ROAD							
10+00.00 TO 11+95.11		194.0	145.5	17.8	-127.7	0.13	
*EXISTING C. H. 18							
200+50 TO 215+06		991.6	743.7	234.8	-508.9	5.17	1622
TOTALS	613.4	15742.3	12266.7	12465.3	198.5	17.9	1622

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULES

SCALE: VERT. HORIZ. DATE 02/28/2008 DRAWN BY RLH CHECKED BY MED

TUG PROJ. #1397022-5  
...WHITE TOPPING SCHEDULES.DGN