

ENTRANCES AND SIDE ROADS
 STATION 46 + 00 A.H. THRU STATION 120 + 00

STATION	WIDTH	COMMENT	P.E. / F.E. OR SIDE ROAD	SUB-BASE GRAN. MAT. TY. B TON	PCC PAVEMENT 8" SQ YD	PCC DRIVEWAY PVT. 8" SQ YD	AGG. SURF. CSE. TY. B TON
---------	-------	---------	--------------------------------	--	-----------------------------	-------------------------------------	------------------------------------

49 + 78 LT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
69 + 60 RT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
71 + 30 RT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
74 + 00 RT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
82 + 54 RT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
89 + 95 RT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
91 + 57 RT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
97 + 61 RT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
108 + 48 LT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
109 + 08 LT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
113 + 15 RT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
118 + 40 LT.	20'	C.H. 18	F.E.	6.0	N/A	16.4	20.0
119 + 67 LT.	20'	C.H. 18	* P.E.	58.0	N/A	231.2	N/A
42 + 88 RT.	20'	T.R. 14	F.E.	N/A	N/A	N/A	10.0
TR 14	20'	APRON	Side Road	10.0	31.1	N/A	N/A
TR 14 A	14'	APRON	Side Road	11.0	34.6	N/A	27.0
				TOTAL = 151.0	TOTAL = 65.7	TOTAL = 428.0	TOTAL = 277.0

