

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	**	MACON	106	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
** 05-00525-00SW				

SUMMARY OF QUANTITIES

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CITY OF DECATUR	MILLIKIN UNIVERSITY
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12	12	
2010020	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42	42	
20200100	EARTH EXCAVATION	CU YD	1170	1170	
20400800	FURNISHED EXCAVATION	CU YD	885	885	
20800150	TRENCH BACKFILL	CU YD	497	497	
2101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3312	3312	
* 25200700	SODDING, SPECIAL	SQ YD	3312	3312	
* 25200200	SUPPLEMENTAL WATERING	UNIT	100	100	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	68	68	
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	383	383	
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	113.6	113.6	
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SQ YD	584	584	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	482	482	
40600300	AGGREGATE (PRIME COAT)	TON	7	7	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	40	40	
40600995	TEMPORARY RAMP, SPECIAL	SQ YD	149	149	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	106	106	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	460	460	
42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	59	59	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	252	252	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	320	320	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	31966	30648	1318
42400500	PORTLAND CEMENT CONCRETE SIDEWALK, SPECIAL	SQ FT	3463	3463	
42400800	DETECTABLE WARNINGS	SQ FT	304	304	
44000100	PAVEMENT REMOVAL	SQ YD	1781	1781	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 11/2"	SQ YD	4766	4766	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	4694	4694	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	879	810	69
44000300	CURB REMOVAL	FOOT	1012	1012	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3899	3899	
44000600	SIDEWALK REMOVAL	SQ FT	27443	26823	620
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	68	68	

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CITY OF DECATUR	MILLIKIN UNIVERSITY
50300254	RUBBED FINISH	SQ FT	40	40	
50901760	PIPE HANDRAIL	FOOT	1007	1007	
550A0050	STORM SEWERS, CLASS A, TYPE 112"	FOOT	284	284	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	450	450	
55100500	STORM SEWER REMOVAL 12"	FOOT	195	195	
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	5	5	
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1	
60219100	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 9 FRAME AND GRATE	EACH	1	1	
60219300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	2	2	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	7	7	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2	
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	6	6	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	5	5	
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1	
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	3	3	
60255500	MANHOLES TO BE ADJUSTED	EACH	6	6	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	
60260100	INLETS TO BE ADJUSTED	EACH	1	1	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	7	7	
60266800	VALVE BOXES TO BE REPLACED	EACH	1	1	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2	2	
60500040	REMOVING MANHOLES	EACH	2	2	
60500050	REMOVING CATCH BASINS	EACH	1	1	
60500060	REMOVING INLETS	EACH	14	14	
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	8	8	

* SPECIALTY ITEMS

REV. NO.	DESCRIPTION	BY	DATE	APPROVED
SUMMARY OF QUANTITIES				
DESIGN BWC	WEST MAIN STREET PHASE II CITY OF DECATUR			SCALE
DATE				BWC PROJECT NO. 009-0605
DRAWN	BWC BLANK, WESSELINK, COOK & ASSOCIATES, INC.			DATE
DATE				SHEET 1 OF 3
CHECKED	ARCHITECTS ENGINEERS			
APPROVED	2623 EAST PERSHING ROAD DECATUR, IL 62524 (217) 428-0973 FAX (217) 428-8934			
DATE				
CLIENT				
APPR.				
DATE				