

SUMMARY OF QUANTITIES

CONTRACT NO. 97325

**THOUVENOT,
WADE &
MOERCHEN, INC.**
ENGINEERS ♦ SURVEYORS ♦ PLANNERS



CORPORATE OFFICE
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6688
corp@twm-inc.com

WATERLOO OFFICE
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5050
FAX (618) 939-3938
waterloo@twm-inc.com

ST. LOUIS OFFICE
1001 CRAIG ROAD, SUITE 260
ST. LOUIS, MISSOURI 63146
TEL (314) 236-5052
FAX (314) 872-2194
stlouis@twm-inc.com

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ILLINOIS PROFESSIONAL DESIGN FIRM	184-001220
PROFESSIONAL ENGINEERING CORP.	62-035370
PROFESSIONAL STRUCTURAL ENGR. CORP.	81-005202
ILLINOIS PROF. LAND SURVEYING CORP.	048-000029
MISSOURI PROFESSIONAL ENGR. CORP.	NC 001528
MISSOURI LAND SURVEYING CORP.	NC 000346

SEAL

Signature: _____
Signature Date: _____
Expiration Date: _____

STATEMENT OF RESPONSIBILITY
I hereby confirm that the document herein to be authenticated by my seal is restricted to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be utilized for any other part of the architectural, engineering or survey project.

CODE NO	ITEM	UNIT	1000-2A TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				-	-
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	51		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	48		
20200100	EARTH EXCAVATION	CU YD	2,079		
20800150	TRENCH BACKFILL	CU YD	146		
25000200	SEEDING, CLASS 2	ACRE	0.7		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63		
25100115	MULCH, METHOD 2	ACRE	0.7		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	160		
28000500	INLET AND PIPE PROTECTION	EACH	10		
28100107	STONE RIPRAP, CLASS A4	SQ YD	20		
28200200	FILTER FABRIC	SQ YD	20		
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	3,068		
30201500	LIME	TON	59		
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	64		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	163		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,072		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	277		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	35		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	403		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	220		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	4,659		
42400800	DETECTABLE WARNINGS	SQ FT	48		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	577		
44000400	GUTTER REMOVAL	FOOT	535		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	159		
44000600	SIDEWALK REMOVAL	SQ FT	2,570		
50105220	PIPE CULVERT REMOVAL	FOOT	221		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1		
54223447	REMOVE AND RELAY PIPE CULVERTS 12"	FOOT	20		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	376		
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	258		
60218500	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1		
60219540	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2		
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	3		
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	3		
60500050	REMOVING CATCH BASINS	EACH	1		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,690		
67100100	MOBILIZATION	L SUM	1		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	352		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,538		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	146		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	65		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	792.0		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	21.5		
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	45		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,538		

* SPECIALTY ITEMS

CODE NO	ITEM	UNIT	1000-2A TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				-	-
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	146		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	65		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	450		
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	44		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	11		
X0321690	BRICK WALL REMOVAL	FOOT	4		
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	823		
X4020500	AGGREGATE SURFACE COURSE, TYPE B 6"	SQ YD	316		

* SPECIALTY ITEMS

LOT DATE = 1/9/2008
FILE NAME = P:\01002585.dgn
LOT SCALE = 56.48000 / IN
SER NAME = machner, john

SUMMARY OF QUANTITIES

**SEIBERT ROAD
RECONSTRUCTION - PHASE II
VILLAGE OF SHILOH
ST. CLAIR COUNTY, ILLINOIS**

REV.	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY: MLS	SHEET
DESIGNED BY: MJJ	3
CHECKED BY: XXX	
APPROVED BY: XXX	
PROJECT NUMBER: T20010479	
OF 35 SHEETS	
<input type="checkbox"/> ISSUED FOR REVIEW	<input type="checkbox"/> ISSUED FOR BIDDING
<input type="checkbox"/> ISSUED FOR CONSTR.	<input type="checkbox"/> RECORD DRAWING