

SUMMARY OF QUANTITIES

Item Number	Item Description	Unit of Measure	Quantity
AR110502	2-WAY CONCRETE ENCASED DUCT	LINEAR FOOT	108.0
AR110504	4-WAY CONCRETE ENCASED DUCT	LINEAR FOOT	125.0
AR150510	ENGINEER'S FIELD OFFICE	LUMP SUM	1.0
AR150530	TRAFFIC MAINTENANCE	LUMP SUM	1.0
AR152410	UNCLASSIFIED EXCAVATION	CUBIC YARD	80,700.0
AR152442	OFFSITE BORROW EXCAVATION	CUBIC YARD	57,280.0
AR152460	TOPSOIL STRIPPING	CUBIC YARD	43,400.0
AR156510	SILT FENCE	LINEAR FOOT	6,337.0
AR156511	DITCH CHECK	EACH	29.0
AR156544	RIPRAP - GRADATION NO. 4	SQUARE YARD	508.0
AR163000	TEMPORARY CONSTRUCTION FENCE	LINEAR FOOT	2,010.0
AR701224	24" CMP	LINEAR FOOT	167.0
AR701512	12" RCP, CLASS IV	LINEAR FOOT	352.1
AR701515	15" RCP, CLASS IV	LINEAR FOOT	38.0
AR701518	18" RCP, CLASS IV	LINEAR FOOT	280.0
AR751540	MANHOLE 4'	EACH	4.0
AR752412	PRECAST REINFORCED CONC. FES 12"	EACH	5.0
AR752415	PRECAST REINFORCED CONC. FES 15"	EACH	3.0
AR752418	PRECAST REINFORCED CONC. FES 18"	EACH	2.0
AR752512	GRATING FOR CONC. FES 12"	EACH	5.0
AR752515	GRATING FOR CONC. FES 15"	EACH	3.0
AR752518	GRATING FOR CONC. FES 18"	EACH	2.0
AR803001	OUTLET WEIR	LUMP SUM	1.0
AR803002	SEEDING - MIXTURE 2A	ACRE	4.3
AR803003	SEEDING, NATIVE MIX	ACRE	3.8
AR803004	CLEARING TREE 0-6" DBH	EACH	16.0
AR803005	CLEARING TREE 6"-15" DBH	EACH	6.0
AR803006	CLEARING TREE OVER 15" DBH	EACH	7.0
AR803007	STUMP REMOVAL 0-6" DBH	EACH	16.0
AR803008	STUMP REMOVAL 6"-15" DBH	EACH	6.0
AR803009	STUMP REMOVAL OVER 15" DBH	EACH	7.0
AR803010	OVERFLOW SPILLWAY	LUMP SUM	1.0
AR803011	INLET - SPECIAL	EACH	2.0
AR803012	TEMPORARY DITCHES	EACH	14.0
AR803013	EROSION MAT - DITCH BOTTOM	SQUARE YARD	1,115.0
AR803014	CONCRETE CABLE BOTTOM	SQUARE YARD	611.0
AR803015	TEMPORARY PAVEMENT	SQUARE YARD	34.0
AR803016	FILL SAND	TON	84,920.0
AR803017	CONSTRUCTION ENTRANCE	EACH	2.0
AR803018	CONSERVATION COVER	ACRE	13.3
AR803020	REMOVE CLASS C FENCE	LINEAR FOOT	240.0
AR905510	TOPSOILING (FROM ON-SITE)	CUBIC YARD	11,600.0
AR908510	MULCHING	ACRE	21.4

Hanson Professional Services Inc.
 Suite 200, 815 Commons Drive
 Oak Brook, Illinois 60521
 © Copyright Hanson Professional Services Inc. 2008



FILE NAME =	USER NAME = Blair01219	DESIGNED - CBP	REVISED -	VILLAGE OF LAKE IN THE HILLS, ILLINOIS	SUMMARY OF QUANTITIES	COUNTY	TOTAL SHEETS	SHEET NO.
I:\05Jobs\00041\0508021\Civil Part A\Sheet	ss\NC-SUM-QUANT.SHT	DRAWN - CBP	REVISED -			MCHENRY	120	3
PLOT SCALE = 2.0000' / 1"	CHECKED - BLB	REVISED -	SCALE:			FEDERAL AIP NO. 3-17-0112-BB	ILLINOIS	IDA NO. 30K-3671
PLOT DATE = 02/27/2008, 09:16 AM	DATE - 02/29/08	REVISED -						