LK005

4'-4" | 60'-0" | 172'-9"

EXIST. MCDOT ROW | PROP. MCDOT ROW

℄ PROP. PYOTT RD.

MATCHLINE=EXISTING PYOTT ROAD

VILLAGE PROPERTY

PROP. MCDOT ROW

PROPOSED GROUND

EXISTING GROUND

8:1 | 25:1 | 6:1 | 3:1

876.98 | 876.52 | 874.87

895 | 890 | 885 | 880 | 875 | 870 | 865

17+00.00

TOPSOIL CUT = 88.7 SQ FT
TOPSOIL FILL = 30.6 SQ FT
SAND FILL = 0.0 SQ FT

UNCLASSIFIED CUT = 17.5 SQ FT
UNCLASSIFIED FILL = 379.6 SQ FT

VERTICAL SCALE IN FEET (1"=5')
5 0 5 10

HORIZONTAL SCALE IN FEET (1"=10')
10 0 10 20

110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160 170 180 190

HANSON
Hanson Professional Services Inc.

FINAL SURVEY
NOTE BOOK
NO.
SURVEYED
PLOTTED
TEMPLATE
AREAS
AREAS CHECKED
BY
DATE

ORIGINAL SURVEY
NOTE BOOK
NO.
SURVEYED
PLOTTED
TEMPLATE
AREAS
AREAS CHECKED
BY
DATE

FILE NAME = I:\05Jobs\00841\0588021\Civil Part A\Sheets\CROSSSECTIONS.sht	USER NAME = Pisar01256	DESIGNED - CBP	REVISED -
		DRAWN - CBP	REVISED -
	PLOT SCALE = 20.0000 ' / IN.	CHECKED - BLB	REVISED -
	PLOT DATE = 02\28\2008 09:52 AM	DATE - 02/29/08	REVISED -

VILLAGE OF LAKE IN THE HILLS, ILLINOIS

CROSS SECTIONS
PROPOSED PYOTT ROAD

SCALE: AS SHOWN | STA. 17+00.00 TO STA. 17+00.00

COUNTY	TOTAL SHEETS	SHEET NO.
MCHENRY	120	48

FEDERAL AIP. NO. 3-17-0112-88 | ILLINOIS | IDA NO. 3CK-9671