

INDEX OF SHEETS:

NO.	DESCRIPTION
1	COVER SHEET
2-4	LOCATION MAPS
5	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES
6	SUMMARY OF QUANTITIES
7	SCHEDULE
8-30	SIGN STRUCTURE DETAILS
31-33	SOIL BORING LOG SHEETS

HIGHWAY STANDARDS:

720021-02	SIGN PANELS EXTRUDED ALUMINUM TYPE
701101-04	OFF-RD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701106-02	OFF-RD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
701400-07	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-08	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-08	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS >= 45 MPH
701451-02	RAMP CLOSURE FREEWAY/EXPRESSWAY
701456-03	PARTIAL EXIT RAMP CLOSURE FREEWAY/EXPRESSWAY
701701-09	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701901-03	TRAFFIC CONTROL DEVICES

NOTES:

STRUCTURE 275: REMOVAL OF OVERHEAD SIGN STRUCTURE- MONOTUBE, SPAN:  
THIS WORK SHALL INCLUDE DELIVERY OF EXISTING SIGNS TO THE DECATUR  
YARD UPON THE REMOVAL OF THE SIGNS. THIS WORK WILL BE PAID FOR AT THE  
CONTRACT UNIT PRICE FOR REMOVAL OF OVERHEAD SIGN STRUCTURE-MONOTUBE-SPAN,  
NECESSARY TO COMPLETE THE WORK.

STRUCTURE 236: CAPPING OF UNUSED CONDUIT CONNECTION POINTS:  
THE CONTRACTOR SHALL REMOVE ANY MATERIAL LOCATED INSIDE THE CHORD OR END  
SUPPORT PRIOR TO INSTALLING THE NEW CAP.

STRUCTURE 269 & 236: OVERHEAD SIGN SUPPORT GROUT REPAIR:  
SHALL INCLUDE UNCOVERING THE BASE PLATES.

RODENT SHIELD/METAL FOUNDATION SCREENS AT ALL LOCATIONS WHERE REQUIRED:  
SHALL NOT BE INSTALLED AT REQUIRED LOCATIONS UNTIL FOUNDATION REPAIR AND/OR  
OVERHEAD SIGN TRUSS PAINTING IS COMPLETED.

FILE NAME =	USER NAME = staffannk	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES, INDEX OF SHEETS, HIGHWAY STANDARDS &amp; COMMENTS</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\p\work\spidat\staffannk\d032093310	6306-ahg-gannote.dgn	DRAWN -	REVISED -				*	**	47	5
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			*0-7 DVD SIN STR REPL 14-42		CONTRACT NO. 46306		
	PLOT DATE = 2/6/2014	DATE -	REVISED -			SCALE:	SHEET OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT **EFFINGHAM, MACON, COLES	