

Location No.:	7-01	State I.D. No.:	42 275				
County:	MACON	Route:	IL 48	STA.	156+18	Direction:	NB
LOCATION NO.:							
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE, MONOTUBE - SPAN	EACH	1.00					
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2.00					

Location No.:	7-04	State I.D. No.:	36 269				
County:	MACON	Route:	BUS 51	STA.	116+61	Direction:	EB
LOCATION NO.:							
Description of Work	Unit	Quantity					
REPLACE HANDHOLE COVER	EACH	1.00					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	2.00					
METAL SCREEN	EACH	2.00					
CLEANING AND PAINTING SIGN STRUCTURE NO. 4	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SO FT	200.00					

Location No.:	7-07	State I.D. No.:	7C058U051L118.9				
County:	MACON	Route:	US 51	STA.	N/A	Direction:	SB
LOCATION NO.:							
Description of Work	Unit	Quantity					
PAINT OVERHEAD SIGN SUPPORT	EACH	1.00					
METAL SCREEN	EACH	1.00					
SAFETY CHAIN	EACH	2.00					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	1.00					
REMOVE AND REINSTALL SIGN PANEL	SO FT	84.00					
TIGHTEN CANTILEVER CONNECTION	EACH	1.00					

Location No.:	7-02	State I.D. No.:	SN 750251070L099.5				
County:	EFFINGHAM	Route:	1-70	STA.	2434+20	Direction:	WB
LOCATION NO.:							
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5' - 0" X 7' - 0")	FOOT	88.00					
OVERHEAD SIGN STRUCTURE - WALKWAY, TYPE A	FOOT	23.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.50					
SIGN LIGHTING (HIGH PRESSURE SODIUM)	EACH	1.00					
REMOVE AND REINSTALL SIGN PANEL	SO FT	173.00					

Location No.:	7-05	State I.D. No.:	22 236				
County:	MACON	Route:	US 36	STA.	RT 277+20	Direction:	SB
LOCATION NO.:							
Description of Work	Unit	Quantity					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	2.00					
METAL SCREEN	EACH	2.00					
REPLACE HANDHOLE COVER	EACH	1.00					
REPL & TIGHTEN SIGN MOUNT CLIPS PER EACH SIGN	EACH	4.00					
CAP UNUSED CONDUIT CONNECTION POINTS	EACH	4.00					
SIGN SUPPORT BRACKET	EACH	8.00					

Location No.:	7-08	State I.D. No.:	7C0151057R189.7				
County:	COLES	Route:	1-57	STA.	788+72	Direction:	NB
LOCATION NO.:							
Description of Work	Unit	Quantity					
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00					
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE III-C-A (36" x 7' - 0")	FOOT	30.00					
OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	20.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	7.50					
RELOCATE ELECTRIC SERVICE	EACH	1.0					
INSTALL SIGN PANEL-TYPE 3	SO FT	133					
SIGN LIGHTING (HIGH PRESSURE SODIUM)	EACH	1.00					

Location No.:	7-03	State I.D. No.:	SN 750251070R090.9				
County:	EFFINGHAM	Route:	1-70	STA.	1980+84	Direction:	EB
LOCATION NO.:							
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5' - 0" X 7' - 0")	FOOT	88.00					
OVERHEAD SIGN STRUCTURE - WALKWAY, TYPE A	FOOT	23.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.30					
SIGN LIGHTING (HIGH PRESSURE SODIUM)	EACH	1.00					
REMOVE AND REINSTALL SIGN PANEL	SO FT	173.00					

Location No.:	7-06	State I.D. No.:	7C058U051L117.4				
County:	MACON	Route:	US 51	STA.	N/A	Direction:	SB
LOCATION NO.:							
Description of Work	Unit	Quantity					
PAINT OVERHEAD SIGN SUPPORT	EACH	1.00					
REPLACE WALKWAY SUPPORT BRACKET BOLT	EACH	5.00					
REPAIR HANDRAILLOCKING PIN CONNECTION	EACH	2.00					
SAFETY CHAIN	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SO FT	180.00					
TIGHTEN CANTILEVER CONNECTION	EACH	1.00					

Location No.:	7-07	State I.D. No.:	7C058U051L118.9				
County:	MACON	Route:	US 51	STA.	N/A	Direction:	SB
LOCATION NO.:							
Description of Work	Unit	Quantity					
PAINT OVERHEAD SIGN SUPPORT	EACH	1.00					
REPLACE WALKWAY SUPPORT BRACKET BOLT	EACH	5.00					
REPAIR HANDRAILLOCKING PIN CONNECTION	EACH	2.00					
SAFETY CHAIN	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SO FT	180.00					
TIGHTEN CANTILEVER CONNECTION	EACH	1.00					