

PROPOSED LEGEND

(1) PORTLAND CEMENT CONCRETE PAVEMENT 10¹/₂" (JOINTED) 2 AGGREGATE SUBGRADE IMPROVEMENT 12" 3 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (4) CONCRETE MEDIAN TYPE SB-6.24 (MODIFIED) (SEE DETAIL) 5 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH 6 TOPSOIL FURNISH AND PLACE 4" (TOPSOIL FURNISH AND PLACE 8" WILL BE USED IN ALL AREAS WHERE TREES WILL BE INSTALLED) (7) SODDING, SALT TOLERANT (8) HOT-MIX ASPHALT (FULL DEPTH), 121/2" -HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, (IL-9.5MM) (2") HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 (10.5") (9) GEOTECHNICAL FABRIC FOR GROUND STABILIZATION (1) BITUMINOUS MATERIALS (PRIME COAT) AND AGGREGATE (PRIME COAT) (1) CONCRETE BARRIER, SINGLE FACE, 34" HEIGHT AND CONCRETE BARRIER BASE (SEE DETAIL) (12) PARAPET RAILING, SPECIAL (13) BICYCLE RAILING, SPECIAL (14) TOPSOIL FURNISH AND PLACE 24" (15) AGGREGATE BASE COURSE, TYPE B, 6" (16) NOISE ABATEMENT WALL, GROUND MOUNTED (17) CAST IN PLACE RETAINING WALL (18) TEMPORARY SHEETING (USED TO ACCOMMODATE UTILITY RELOCATION) (19) HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (3") 20 AGGREGATE BASE COURSE, TYPE B 2) GRANULAR BACKFILL FOR STRUCTURES (2) LONGITUDINAL SAWED JOINT, NO. 8 EPOXY COATED TIE BARS, 30" LONG AT 30" CENTERS, DRILL AND GROUT (INCLUDED IN COST OF PCC PAVEMENT 23 LONGITUDINAL CONSTRUCTION JOINT, NO. 8 EPOXY COATED TIE BARS, 24" LONG AT 24"CENTERS 2 BARRIER WALL MARKERS, TYPE B AT 40' CENTERS DRILL AND GROUT NO. 8 EPOXY COATED TIE BARS, 24" LONG AT 24" CENTERS (INCLUDED IN THE COST OF CONCRETE MEDIAN TYPE SB-6.24 (MODIFIED) AND COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24) \bigotimes Reinforced select fill for temporary mechanically stabilized earth retaining wall (included in the cost of temporary mse wall) 27 SOLDIER PILE RETAINING WALL (28) TOPSOIL FURNISH AND PLACE 12" 29 AGGREGATE BASE COURSE, TYPE B 8" (31) EROSION CONTROL BLANKET (SPECIAL)

AL SECTIONS			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
			311	652-A	DUPAGE	383	28	
				CONTRACT NO. 60R06			0R06	
5	STA.	TO STA.	FED. RO	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				