

TEMPORARY PIPES

PIPE NO.	STR. NO. FROM	STR. NO. TO	DESCRIPTION	IN DIA.	FT LEN	SLOPE	CU YD TBF
T20	T01	T02	SS, CL A, TY 2	12	137.0	0.57%	41.0
T21	T02	T03	SS, CL A, TY 2	12	129.0	0.55%	41.3
T22	T03	T04	SS, CL A, TY 2	12	137.0	0.56%	49.6
T23	T04	T05	SS, CL A, TY 2	12	142.0	0.47%	51.4
T24	T05	T06	SS, CL A, TY 2	12	86.0	0.42%	16.7
T25	T01	EX	SS, CL A, TY 2	12	3.0	0.50%	1.0
T26	T02	EX	SS, CL A, TY 2	12	3.0	0.50%	1.0
T27	T03	EX	SS, CL A, TY 2	12	3.0	0.50%	1.0
T28	T04	EX	SS, CL A, TY 2	12	3.0	0.50%	1.0
T29	T05	EX	SS, CL A, TY 2	12	3.0	0.50%	1.0
T30	T06	EX	SS, CL A, TY 2	12	70.0	0.50%	9.3
T70	T50	T51	SS, CL A, TY 2	12	198.0	0.44%	26.1
T71	T51	T52	SS, CL A, TY 2	12	88.0	0.45%	11.6
T72	T52	T53	SS, CL A, TY 2	12	117.0	0.44%	15.4
T73	T53	T54	SS, CL A, TY 2	12	128.0	0.44%	16.9
T74	T54	T55	SS, CL A, TY 2	12	126.0	0.44%	16.6
T75	T55	T56	SS, CL A, TY 2	12	108.0	0.47%	14.3
T76	T56	EX	SS, CL A, TY 2	12	46.0	1.35%	6.1

PAID FOR AS TEMPORARY STORM SEWER, CLASS A, TYPE 2, 12"

TEMPORARY STRUCTURES

STR. NO.	STA.	OFFSET	MH*	TC=2' TA=4' CB	INL	OTHER	FRAME AND GRATE	N	S	E	W	RIM ELEV.
T01	123+21.0	50.0	RT	4			T-1-OL				703.77	709.91
T02	121+82.0	50.0	RT	4			T-1-OL			702.99	702.97	708.73
T03	120+50.0	50.0	RT	4			T-1-OL			702.26	702.24	708.77
T04	119+10.0	50.0	RT	4			T-1-OL			701.47	701.45	708.32
T05	117+65.0	50.0	RT	4			T-1-OL			700.78	700.77	707.30
T06	116+75.9	50.0	RT	4			T-1-OL	700.28		700.41		704.11
T50	125+50.0	45.0	RT	4			T-1-OL			708.68		711.68
T51	127+50.0	45.0	RT	4			T-1-OL			707.79	707.81	711.99
T52	128+41.4	46.5	RT	4			T-1-OL			707.39	707.39	711.56
T53	129+61.4	49.0	RT	4			T-1-OL			706.86	706.88	710.93
T54	130+91.8	49.0	RT	4			T-1-OL			706.29	706.30	710.34
T55	132+21.4	49.0	RT	4			T-1-OL			705.71	705.73	709.79
T56	133+31.6	54.1	RT	4			T-1-OL	705.20			705.20	709.39

• PAID FOR AS TEMPORARY MANHOLE

FILE NAME = Q:\DOT_25368367_US_34.ctb\Drawings\Roadway\Drainage\Utility\1616106-TempSchedule.dgn

URS	USER NAME = URS	DESIGNED - MB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY DRAINAGE SCHEDULE		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - KJB	REVISED -	311				652-A		383	63	
	PLOT SCALE = 100.0000' / in.	CHECKED - SPF	REVISED -				CONTRACT NO. 60R06				
PLOT DATE = 02/28/2014	DATE - 02/28/2014	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				