

FILE NAME : D:\1001_25362617_05_34.ctb P:\2\Drawings\Roadway\General\101028206-Sht-500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							TRAFFIC SIGNALS	SHARED-USE TRAIL	100 % AURORA
				67% CANADIAN NATIONAL RAILROAD 33% STATE					67 % CN 23% STATE 10% AURORA	80% STATE 20% FVPD +			
				ROADWAY	BRIDGE	RETAINING WALLS			NOISE WALL				
				0001 URBAN	0008 URBAN	0040 URBAN			0040 URBAN	0021 URBAN			
				S. N. 022-0512	S. N. 022-W068	S. N. 022-W069	S. N. 022-W070	S. N. 022-W071			0043 URBAN		
50200100	STRUCTURE EXCAVATION	CU YD	8508		1448	1762	1324	1849	2125				
50300225	CONCRETE STRUCTURES	CU YD	7842.1		2340.3	1220.8	1114.1	1543.2	1623.7				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1228.7		1228.7								
50300260	BRIDGE DECK GROOVING	SO YD	2033		2033								
50300285	FORM LINER TEXTURED SURFACE	SO FT	39784		3159	8525	7278	10116	10706				
50300300	PROTECTIVE COAT	SO YD	4915		4915								
50500305	ERECTING STRUCTURAL STEEL	L SUM	1		1								
50500505	STUD SHEAR CONNECTORS	EACH	19484		19008	159	173	144					
50800105	REINFORCEMENT BARS	POUND	1476360		199730	310260	225330	355100	385940				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1307890		536980	174600	159420	212070	224820				
50800515	BAR SPLICERS	EACH	1350		1350								
51500100	NAME PLATES	EACH	5		1	1	1	1	1				
* 51603000	DRILLED SHAFT IN SOIL	CU YD	6069		1092	1181	969	1373	1454				
* 51604000	DRILLED SHAFT IN ROCK	CU YD	194		59	25	23	41	46				

* SPECIALTY ITEM

+ FVPD = FOX VALLEY PARK DISTRICT

CN = CANADIAN NATIONAL RAILROAD



USER NAME : URS	DESIGNED - MB	REVISED -
PLOT SCALE : 100.0000' / 1" =	DRAWN - KJB	REVISED -
PLOT DATE : 2/11/2014	CHECKED - SPF	REVISED -
	DATE - 2/11/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652-A	DUPAGE	383	8
CONTRACT NO. 6006			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	