CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				67% CANADIAN NATIONAL RAILROAD 33% STATE							67 % CN 23%STATE 10% AURORA	80% STATE 20% FVPD +	100 % AURORA
				ROADWAY	BRIDGE	RETAINING WALLS				NOISE WALL	TRAFFIC SIGNALS	SHARED-USE TRAIL	
				0001	0008	0040				0040	0021	0028	0043
				URBAN	URBAN	URBAN				URBAN	URBAN	URBAN	URBAN
					S. N. 022-0512	S. N. 022-W068	S. N. 022-W069	S. N. 022-W070	S. N. 022-W071				
58700300	CONCRETE SEALER	SQ FT	7429		7429								
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	5229		993	975	870	1184	1207				
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1									1	
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	20	20									
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1									
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2									
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	2	1								1	
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	32	32									
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	18	18									
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	5	5									
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	7									
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10	10									
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	24	24									
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	3	3									

* SPECIALTY ITEM + FVPD = FOX VALLEY PARK DISTRICT CN = CANADIAN NATIONAL RAILROAD

FILE NAME = D:\1001_2536367_US 34 at CN Ph2\Drawings\Roadway\General\D160R06-Sht-Sod.dgn

URS

USER NAME = URS	DESIGNED - MB	REVISED -	
	DRAWN - KJB	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED - SPF	REVISED -	
PLOT DATE = 2/11/2014	DATE - 2/11/2014	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652-A	DUPAGE	383	11
		CONTRACT NO. 60R06		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT