	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: 67% CANADIAN NATIONAL RAILROAD 33% STATE — ROADWAY 0001 URBAN	BRIDGE 0008 URBAN S.N. 022-0512	RETAINING WALLS 0040 URBAN S.N. 022-W068	S.N. 022-W069	S.N. 022-W070	S.N. 022-W071	NOISE WALL 0040 URBAN	67 % CN 23%STATE 10% AURORA — TRAFFIC SIGNALS 0021 URBAN	80% STATE 20% FVPD + — SHARED-USE TRAIL 0028 URBAN	100 % AURORA 0043 URBAN
*	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5447								5447		
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1532								1532		
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2170								2170		
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2360								2360		
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	880								880		
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2591								2591		
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	153								153		
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	777								777		
*	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1								1		
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2								2		
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2								2		
*	87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1								1		
*	87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1								1		
*	87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1								1		

* SPECIALTY ITEM + FVPD = FOX VALLEY PARK DISTRICT CN = CANADIAN NATIONAL RAILROAD

FILE NAME = D:\1001_25368367_US 34 at CN Ph2\Drawings\Roadway\General\0162R06-Sht-Sa0.dgn

URS

USER NAME = URS	DESIGNED - MB	REVISED -	
	DRAWN - KJB	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED - SPF	REVISED -	
PLOT DATE = 2/11/2014	DATE - 2/11/2014	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652-A	DUPAGE	383	16

CONTRACT NO. 60R06

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT