



NORTHEAST WALL ELEVATIONS 

STATION	E. & W. PGL ELEV.	ELEV. A TOP OF EXPOSED PANEL LINE	ELEV. OF EXIST. GRADE	ELEV. B THEORETICAL TOP OF LEVELING PAD	H (FT.)
276+50.00	644.75	642.77	630.89	625.82	16.95
276+75.00	645.72	643.75	630.93		17.93
276+91.42	646.36	644.39	631.13		18.57
277+00.00	646.70	644.72	631.17		18.90
277+25.00	646.67	645.70	630.75		19.08
277+44.99	648.46	646.49	630.74		20.66
277+50.00	648.65	646.67	630.32		20.85
277+64.32	649.20	647.23	629.84		21.41
277+75.00	649.62	647.65	629.57		21.83
277+83.65	649.96	647.98	629.80		22.16
278+00.00	650.60	648.62	632.63		22.80
278+25.00	651.57	649.60	630.49		23.78
278+50.00	652.55	650.57	629.30		24.75
278+75.00	653.52	651.55	629.30		25.73
279+00.00	654.50	652.52	627.49		26.70
279+25.00	655.47	653.50	631.03		27.68
279+28.33	655.60	653.63	631.03		27.81
279+35.00	655.88	653.90	631.05		28.08
279+50.00	656.44	654.46	631.14		28.64
279+75.00	657.32	655.33	631.20		29.51
280+00.00	658.11	656.11	631.26		30.29
280+25.00	658.82	656.80	631.26		30.98
280+50.00	659.44	657.41	631.29		31.59
280+75.00	659.96	657.92	631.32		32.10
281+00.00	660.41	658.35	631.34		32.53
281+10.52	660.57	658.51	631.30		32.69
281+25.00	660.76	658.70	631.15		32.88
281+44.21	660.97	658.92	629.68		33.10
281+52.27	661.05	652.66	629.41		26.84

NORTHWEST WALL ELEVATIONS 

STATION	E. & W. PGL ELEV.	ELEV. A TOP OF EXPOSED PANEL LINE	ELEV. OF EXIST. GRADE	ELEV. B THEORETICAL TOP OF LEVELING PAD	H (FT.)
274+50.00	636.95	634.78	631.35	627.82	6.96
274+75.00	637.92	635.75	631.46		7.93
275+00.00	638.90	636.73	631.49		8.91
275+25.00	639.87	637.70	631.53		9.88
275+50.00	640.85	638.68	631.58		10.86
275+75.00	641.82	639.65	631.63		11.83
276+00.00	642.80	640.63	631.68		12.81
276+25.00	643.77	641.60	631.75		13.78
276+50.00	644.75	642.58	631.81		14.76
276+75.00	645.72	643.55	632.58		15.73
276+83.09	646.04	643.87	632.65		16.05
276+91.71	646.37	644.21	632.62		16.39
277+00.00	646.70	644.53	632.43		16.71
277+25.00	647.67	645.50	632.95		17.68
277+44.99	648.45	646.28	633.16		18.46
277+50.00	648.65	646.48	633.22		18.66
277+64.32	649.20	647.04	633.36		19.72
277+75.00	649.62	647.45	633.36		20.13
277+83.65	649.96	647.79	633.33	628.82	18.97
278+00.00	650.60	648.43	633.35		19.61
278+25.00	651.57	649.40	633.44		20.58
278+50.00	652.55	650.38	633.27		21.56
278+75.00	653.52	651.35	633.10		22.53
279+00.00	654.50	652.33	632.90		23.51
279+25.00	655.47	653.30	632.90		24.48
279+35.00	655.88	653.71	632.90		24.89
279+50.00	656.44	654.28	632.89		25.46
279+75.00	657.32	655.16	632.88		26.34
280+00.00	658.11	655.95	632.86		27.13
280+25.00	658.82	656.65	632.91		27.83
280+50.00	659.44	657.27	633.04		28.45
280+75.00	659.96	657.80	633.17		28.98
281+00.00	660.41	658.24	633.34		29.42
281+25.00	660.76	658.59	633.40		29.77
281+34.98	660.88	658.71	633.42		29.89
281+43.03	660.96	652.66	633.48		23.84

 V3 Companies of Illinois Ltd. 7325 Janes Avenue Woodridge, IL 60517 830.724.9299 phone 830.724.9202 fax www.v3co.com	USER NAME :	DESIGNED - EVS	REVISED  4/09/2014 W.J.V.	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MSE WALL CROSS SECTION TABLES STRUCTURE NO. 016-1279	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE :	CHECKED - WJV	REVISED			353	11-Y-A	COOK	354	229
	PLOT DATE :	DRAWN - EVS	REVISED			CONTRACT NO. 60R19				
		CHECKED - WJV	REVISED			SHEET NO. 9 OF 35 SHEETS				