

**DRAINAGE & UTILITY STRUCTURE REMOVAL SCHEDULE**

LOCATION	60500040	60500050	60500060	X6050500
	REMOVING MANHOLES EACH	REMOVING CATCH BASINS EACH	REMOVING INLETS EACH	REMOVE FRAME AND GRATE, SPECIAL EACH
US ROUTE 30				
259+00 TO 269+00	3	2	5	1
269+00 TO 280+50	7	3	17	5
280+50 TO 289+25	7	3	13	5
289+25 TO 301+00	6	1	12	5
SAUK TRAIL				
380+00 TO 386+75	0	1	2	0
TOTALS	23	10	49	16

**DRAINAGE & UTILITY STRUCTURE ADJUSTMENT SCHEDULE**


LOCATION	60250200	60255500	60404800	60406000
	CATCH BASINS TO BE ADJUSTED EACH	MANHOLES TO BE ADJUSTED EACH	FRAMES AND GRATE, TY11 EACH	FRAMES AND LIDS, TY1, OL EACH
US ROUTE 30				
260+00 TO 262+00	0	0	0	1
262+00 TO 276+00	0	1	1	8
276+00 TO 289+00	4	0	0	3
289+00 TO 302+00	0	2	0	5
WEST FRONTAGE ROAD NORTH				
100+00 TO 113+75.52	0	2	0	0
WEST FRONTAGE ROAD SOUTH				
401+10 TO 409+70	1	2	0	0
TOTALS	5	7	1	17

**STORM SEWER REMOVAL SCHEDULE**

LOCATION	50105220	55100100	55100500	55100900	55101100	SS REMOVAL 24" (SPECIAL)	SS REMOVAL 27" (SPECIAL)	SS REMOVAL 30" (SPECIAL)	SS REMOVAL 36" (SPECIAL)	SS REMOVAL 42" (SPECIAL)
	PIPE CULVERT REMOVAL FOOT	SS REMOVAL 4" FOOT	SS REMOVAL 12" FOOT	SS REMOVAL 18" FOOT	SS REMOVAL 21" FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
US ROUTE 30										
259+00 TO 269+00	0	0	228	0	0	0	0	0	322	389
269+00 TO 280+50	0	0	674	0	0	0	0	0	324	398
280+50 TO 289+25	111	0	618	0	0	0	169	576	0	0
289+25 TO 301+00	0	26	439	161	145	161	0	0	0	0
SAUK TRAIL										
378+50 TO 387+00	0	0	25	0	0	0	0	0	0	0
TOTALS	111	26	1,984	161	145	161	169	576	646	787

**PROPOSED STORM SEWER SCHEDULE**

LOCATION	20800150	STORM SEWERS, CLASS A, TYPE 2										550A0710	550A4710	550A4720	60107600
	TRENCH BACKFILL CU YD	550A0340 12" FOOT	550A0380 15" FOOT	550A0380 18" FOOT	550A0410 24" FOOT	550A0430 30" FOOT	550A0450 36" FOOT	550A0470 42" FOOT	550A0480 48" FOOT	550A0490 54" FOOT	550A5100 EQV RND SZ 30" FOOT	STORM SEWERS CLASS A, TY 3, 24" FOOT	STORM SEWERS, CL A, TY 1, EQV RND-SIZE 48" FOOT	STORM SEWERS, CL A, TY 1, EQV RND-SIZE 54" FOOT	PIPE UNDERDRAINS, 4" FOOT
US ROUTE 30															
260+00 TO 262+00	642	143	0	0	0	0	0	0	0	0	0	0	0	0	
262+00 TO 276+00	88	418	0	252	302	33	0	13	0	266	0	13	94	204	
276+00 TO 289+00	507	1,032	106	165	571	0	0	0	0	0	0	0	0	0	
289+00 TO 302+00	624	360	33	31	494	0	0	0	0	0	0	0	0	0	
SAUK TRAIL															
380+00 TO 386+75	302	339	0	0	0	109	0	0	0	0	81	0	0	0	
WEST FRONTAGE ROAD NORTH															
100+00 TO 113+75.52	1,135	421	0	0	26	62	182	0	199	174	0	0	311	0	
WEST FRONTAGE ROAD SOUTH															
401+10 TO 409+70	1,081	468	77	0	205	0	803	0	0	0	0	0	0	50	
TOTALS	4,379	3,181	216	448	1,599	204	985	13	199	440	81	13	405	204	



V3 Companies  
7325 Janes Avenue  
Woodridge, IL 60517  
630.724.9200 phone  
630.724.9202 fax  
www.v3co.com

USER NAME = dsherman  
DESIGNED - DSS  
DRAWN - DRP  
CHECKED - VJD  
DATE - 02/21/2014  
REVISOR -  
REVISION -  
REVISOR -  
REVISION -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES  
SCALE: N/A SHEET NO. 4 OF 9 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	11-Y-A	COOK	354	31
CONTRACT NO. 60R19				
ILLINOIS FED. AID PROJECT				