

In order to alleviate dowdrag on pile, the Contractor

Construct the MSE walls first, wait **6 months, and then drive piles through sleeves that were placed before MSE wall construction. Place sleeves after removal of unsuitable material and before backfilling with Aggregate Subgrade Improvement where this is necessary. Cost included with Furnishing Metal Shell Piles, 14" \$\phi\$ x 0.25".


**Or until the settlement platforms for the MSE walls indicate that 1.6" of the estimated 2.0" of settlement has occurred at the abutment.

Hatched area to be poured after superstructure forms have been removed. Quantity of concrete included with Concrete Superstructure.

Space reinforcement in cap to miss anchor bolts. Bar indicated thus 4x2-#5 etc. indicates 4 lines of bars with 2 lengths per line.

See Sheet 22 of 35 for Sec. Thru North Abut., Anchor Bolt Detail I, Bar Details, and Bill of Material. See Sheet 11 of 35 for median and parapet reinforcement details.

See Sheet 24 of 35 for additional pile information. See sheet 25 of 35 for details of Bar Splicers.



	V3 Companies of Hillnols Ltd.
/ >	7325 Janes Avenue
	Woodridge, IL 60517
	630.724.9200 phone
\ \ \	630.724.9202 fax
	www.v3co.com

USER NAME =	DESIGNED - WJV	REVISED
	CHECKED - CJB	REVISED
PLOT SCALE =	DRAWN - WJV	REVISED
PLOT DATE =	CHECKED - CJB	REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

NORTH ABUTMENT	F.A.P. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
	353	11-Y-A		соок	354	205
STRUCTURE NO. 016-1350				CONTRAC	T NO.	60R19
SHEET NO. 20 OF 35 SHEETS		ILLINO	S FED. A	ID PROJECT		