


ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	78.5% CN / 21.5% STATE						80% STATE	80% STATE
				ROADWAY	CN RR BRIDGE	3-SIDED CULVERT	TRAFFIC SIGNALS	RETAINING WALLS	BIKEPATH	SIDEWALK	
				0003	0008	0008	0021	0040	0028	0021	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	133	133							
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,812	2,812							
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	827	162					665		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	75	75							
40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SO YD	8305	8305							
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SO YD	3,590	3,590							
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	22,560	22,560							
42001300	PROTECTIVE COAT	SO YD	10,847	10,847							
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	800	800							
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	426	426							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	1623	1623							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	9352							9352	
42400800	DETECTABLE WARNINGS	SO FT	293	293							
44000100	PAVEMENT REMOVAL	SO YD	24,554	24,554							
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	14.932	14.932							
44000300	CURB REMOVAL	FOOT	801	801							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	12,311	12,311							
44000600	SIDEWALK REMOVAL	SO FT	124	124							
44003100	MEDIAN REMOVAL	SO FT	2,162	2,162							
44004250	PAVED SHOULDER REMOVAL	SO YD	175	175							
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	75	75							

• SPECIALTY ITEM



USER NAME * hahah	DESIGNED - DSS	REVISED -
PLCT SCALE * 1:8000 1/4"	DRAWN - DRP	REVISED -
PLOT DATE * 8/21/2013	CHECKED - VJD	REVISED -
	DATE - 08/14/2013	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 3 OF 15 SHEETS

F.A.P. RTE. 353	SECTION II-Y-A	COUNTY COOK	TOTAL SHEETS 354	SHEET NO. 6
CONTRACT NO. 60R19				
ILLINOIS FED. AID PROJECT				

Rev.