


FILE NAME = S:\JULI6330-6399\624\625\Ncr-ba\ACAD\ Sheets\60W13.dwg - 500.dwg

| CODE NO. | ITEM  | UNIT   | TOTAL QUANTITY | CONSTRUCTION CODE              |                         |                          |                          |  |                    |                    |                                      |  |  |
|----------|---|--------|----------------|--------------------------------|-------------------------|--------------------------|--------------------------|--|--------------------|--------------------|--------------------------------------|--|--|
|          |   |        |                | 80% FED 20% STATE ROADWAY 0004 | 100% STATE ROADWAY 0004 | 80% FED 20% STATE RAMP B | 80% FED 20% STATE RAMP D | 80% FED 10% STATE 10% JOLIET VOYAGER LN. | 100% JOLIET RAMP B | 100% JOLIET RAMP D | 80% FED 20% STATE INTER-CONNECT 0021 | 80% FED 20% STATE STREET LIGHTING 0021 |  |
| URBAN    | URBAN   | URBAN  | URBAN          | URBAN                          | URBAN                   | URBAN                    | URBAN                    | URBAN                                    | URBAN              | URBAN              |                                      |  |  |
| 40300100 | BITUMINOUS MATERIALS (PRIME COAT)                   | GALLON | 2,669          | 2,669                          |                         |                          |                          |  |                    |                    |                                      |  |  |
| 42000416 | PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)  | SQ YD  | 2,869          | 2,869                          |                         |                          |                          |  |                    |                    |                                      |  |  |
| 42001300 | PROTECTIVE COAT                                     | SQ YD  | 4,195          | 4,195                          |                         |                          |                          |  |                    |                    |                                      |  |  |
| 44000100 | PAVEMENT REMOVAL                                    | SQ YD  | 372            | 372                            |                         |                          |                          |  |                    |                    |                                      |  |  |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL                 | FOOT   | 612            | 612                            |                         |                          |                          |  |                    |                    |                                      |  |  |
| 44004250 | PAVED SHOULDER REMOVAL                              | SQ YD  | 1,016          | 1,016                          |                         |                          |                          |  |                    |                    |                                      |  |  |
| 44213200 | SAW CUTS  | FOOT   | 567            | 567                            |                         |                          |                          |  |                    |                    |                                      |  |  |
| 48300415 | PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"           | SQ YD  | 1,227          | 1,227                          |                         |                          |                          |  |                    |                    |                                      |  |  |
| 50105220 | PIPE CULVERT REMOVAL                                | FOOT   | 6              | 6                              |                         |                          |                          |  |                    |                    |                                      |  |  |
| 54213657 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" | EACH   | 1              | 1                              |                         |                          |                          |  |                    |                    |                                      |  |  |
| 54213675 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30" | EACH   | 1              | 1                              |                         |                          |                          |  |                    |                    |                                      |  |  |
| 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12"                   | FOOT   | 27             | 27                             |                         |                          |                          |  |                    |                    |                                      |  |  |
| 550A0380 | STORM SEWERS, CLASS A, TYPE 2 18"                   | FOOT   | 42             | 42                             |                         |                          |                          |  |                    |                    |                                      |  |  |
| 550A0410 | STORM SEWERS, CLASS A, TYPE 2 24"                   | FOOT   | 30             | 30                             |                         |                          |                          |  |                    |                    |                                      |  |  |

\* SPECIALTY ITEM



|                           |                 |           |
|---------------------------|-----------------|-----------|
| USER NAME = B11P          | DESIGNED - JLB  | REVISED - |
| MODEL NAME = Default      | DRAWN - DJW     | REVISED - |
| PLOT SCALE = 2.0000" / 1" | CHECKED - BMA   | REVISED - |
| PLOT DATE = 12/23/2013    | DATE - 12/17/13 | REVISED - |

|                 |           |
|-----------------|-----------|
| DESIGNED - JLB  | REVISED - |
| DRAWN - DJW     | REVISED - |
| CHECKED - BMA   | REVISED - |
| DATE - 12/17/13 | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

| SCALE: | SHEET | OF | SHEETS | STA. | TO STA. |
|--------|-------|----|--------|------|---------|
|        |       |    |        |      |         |

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------|---------|--------|--------------|-----------|
| 575       | 14-N    | WILL   | 163          | 6         |

ILLINOIS FED. AID PROJECT

CONTRACT NO. 60W13