

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				80% FED 20% STATE	100% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% STATE 10% JOLIET	100% JOLIET	100% JOLIET	80% FED 20% STATE	80% FED 20% STATE	
				ROADWAY 0004	ROADWAY 0004	RAMP B	RAMP D	VOYAGER LN.	RAMP B	RAMP D	INTER-CONNECT 0021	STREET LIGHTING 0021	
URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN				
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	19	19									
55100500	STORM SEWER REMOVAL 12"	FOOT	27	27									
55100900	STORM SEWER REMOVAL 18"	FOOT	6	6									
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	3	3									
60107700	PIPE UNDERDRAINS 6"	FOOT	692	692									
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	70	70									
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1									
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
60500040	REMOVING MANHOLES	EACH	1	1									
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	12	12									
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	451	451									
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	229	229									
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	51	51									
60610500	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	68	68									

* SPECIALTY ITEM

FILE NAME: S:\JCL\16300-6399\6316\05\Ntros\CA00 Sheets\60W13-in-500.dgn



USER NAME * B:11P	DESIGNED - JLB	REVISED -
MODEL NAME * DeFouls	DRAWN - DJW	REVISED -
PLOT SCALE * 2.0000 / 1" =	CHECKED - BMA	REVISED -
PLOT DATE * 12/23/2013	DATE - 12/17/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTED	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	14-N	WILL	163	7
CONTRACT NO. 60W13			ILLINOIS FED. AID PROJECT	