


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				80% FED 20% STATE	100% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% STATE 10% JOLIET	100% JOLIET	100% JOLIET	80% FED 20% STATE	80% FED 20% STATE	
				ROADWAY 0004	ROADWAY 0004	RAMP B	RAMP D	VOYAGER LN.	RAMP B	RAMP D	INTER-CONNECT 0021	STREET LIGHTING 0021	
URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	468	468									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2	2									
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1										1
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1										1
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2			1	1						
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	6,865			1,005	951				4,909		
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	295			107	188						
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	1,103			120	102						881
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	849			519	330						
81400100	HANDHOLE	EACH	12			6	6						
81400200	HEAVY-DUTY HANDHOLE	EACH	4			2	2						
81400300	DOUBLE HANDHOLE	EACH	3			2	1						
81603090	UNIT DUCT, 600V, 3-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	4,644										4,644
81800330	AERIAL CABLE, 3-1/C NO. 6 WITH MESSENGER WIRE	FOOT	2,000										2,000

* SPECIALTY ITEM

FILE NAME = S:\JULY2009-03\PROJECTS\100\Network\KODI Express\KODI10-int-500.dgn



1170 SOUTH HOUSLIT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = B11P
MODEL NAME = Default
PLOT SCALE = 2.0000 "/>

DESIGNED - JLB
DRAWN - DJW
CHECKED - BMA
DATE - 12/17/13

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTED	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	14-N	WILL	163	11
			CONTRACT NO. 60W13	
ILLINOIS FED. AID PROJECT				