


FILE NAME = S:\JOL\60300-63\PM\60300\Sheet\60300.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				80% FED 20% STATE	100% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% STATE 10% JOLIET	100% JOLIET	100% JOLIET	80% FED 20% STATE	80% FED 20% STATE	
				ROADWAY 0004	ROADWAY 0004	RAMP B	RAMP D	VOYAGER LN.	RAMP B	RAMP D	INTER-CONNECT 0021	STREET LIGHTING 0021	
				URBAN	URBAN	TRAFFIC SIGNALS 0021			EVP 0021		URBAN	URBAN	
• 87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1			1							
• 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1				1						
• 87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	2			1	1						
• 87702310	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 24 FT. AND 36 FT.	EACH	1			1							
• 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	40			16	24						
• 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8			4	4						
• 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	20			10	10						
• 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	60			36	24						
• 87900200	DRILL EXISTING HANDHOLE	EACH	22								22		
• 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	13			7	6						
• 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	7			4	3						
• 88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	1				1						
• 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2				2						
• 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	6			4	2						

• SPECIALTY ITEM



1170 SOUTH HOBBS ROAD
JOLIET, ILLINOIS 60431
815/744-4200

USER NAME = 011P
MODEL NAME = Default
PLOT SCALE = 2,000' / 1" = 1/2000
PLOT DATE = 12/23/2013

DESIGNED - JLB
DRAWN - DJW
CHECKED - BMA
DATE - 12/17/13

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RT#	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
575	14-N	WILL	163	14
CONTRACT NO. 60W13			ILLINOIS FED. AID PROJECT	